

OFFICE OF ZONING ADMINISTRATION
200 N. SPRING STREET, ROOM 763
LOS ANGELES, CA 90012-4801
(213) 978-1318

ESTINEH MAILIAN
CHIEF ZONING ADMINISTRATOR

ASSOCIATE ZONING ADMINISTRATORS

JACK CHIANG
HENRY CHU
TIM FARGO
JONATHAN A. HERSHEY, AICP
PHYLLIS NATHANSON
CHRISTINE M. SAPONARA
COURTNEY SHUM
CHRISTINA TOY LEE
JORDANN TURNER

CITY OF LOS ANGELES
CALIFORNIA



KAREN BASS
MAYOR

LOS ANGELES DEPARTMENT
OF CITY PLANNING
EXECUTIVE OFFICES

VINCENT P. BERTONI, AICP
DIRECTOR

KEVIN J. KELLER, AICP
EXECUTIVE OFFICER

SHANA M.M. BONSTIN
DEPUTY DIRECTOR

HAYDEE URITA-LOPEZ
DEPUTY DIRECTOR

ARTHI L. VARMA, AICP
DEPUTY DIRECTOR

LISA M. WEBBER, AICP
DEPUTY DIRECTOR

CRAIG R. WEBER
DEPUTY DIRECTOR

planning.lacity.org

April 10, 2026

Last Day to File an Appeal: April 27, 2026

As The Crow, LLC
Hallie Black
2634 6th Street
Santa Monica, CA 90405

CASE NO. ZA-2025-2856-CU1-SPPC-
HCA
Related Case No. ADM-2024-7883-
PMUL
CLASS 1 CONDITIONAL USE PERMIT,
SPECIFIC PLAN PROJECT
COMPLIANCE
1236 North Cliff Drive
Northeast Los Angeles Community Plan
Zone: R1-1-HCR
C.D: 1
D.M.: 147A219
CEQA: ENV-2025-2857-CE
Legal Description: Lot 64, Tract 4085

Pursuant to California Environmental Quality Act, I hereby DETERMINE:

based on the whole of the administrative record, that the Project is exempt from the California Environmental Quality Act (CEQA) pursuant to CEQA Guidelines, Section 15303, Class 3, and there is no substantial evidence demonstrating that any exceptions contained in Section 15300.2 of the State CEQA Guidelines regarding location, cumulative impacts, significant effects or unusual circumstances, scenic highways, or hazardous waste sites, or historical resources applies.

Pursuant to Los Angeles Municipal Code Section 12.24 X.28 of Chapter 1 and Section 13B.2.1. of Chapter 1A, I hereby DENY:

a Class 1 Conditional Use to allow the construction, use, and maintenance of two new single-family dwellings on a lot fronting a Substandard Hillside Limited Street without providing a minimum 20-foot wide roadway adjacent to the property as required by LAMC Chapter 1 Section 12.21 C.10(i)(2); and,

Pursuant to Los Angeles Municipal Code Section 12.24 X.28 of Chapter 1 and Section 13B.2.1. of Chapter 1A, I hereby APPROVE:

Class 1 Conditional Uses to allow

the construction, use, and maintenance of two new single-family dwellings fronting on a Substandard Hillside Limited Street where a minimum 20-foot wide continuous paved roadway is not provided from the driveway apron to the boundary of the Hillside Area, as required by LAMC Chapter 1 Section 12.21 C.10(i)(3);

a reduced front yard setback in lieu of the minimum five feet otherwise required by LAMC Chapter 1 Section 12.21 C.10(a); and,

Pursuant to Los Angeles Municipal Code Section 13B.4.2. of Chapter 1A, and the Mount Washington/Glassell Park Specific Plan Ordinance No. 168,707, I hereby APPROVE:

a Specific Plan Project Compliance for the construction, use, and maintenance of two new single-family dwellings totaling approximately 3,693.83 square feet on an approximately 9,305.80 square-foot vacant hillside lot.

Upon the following additional terms and conditions:

1. All other use, height and area regulations of the Municipal Code and all other applicable government/regulatory agencies shall be strictly complied with in the development and use of the property, except as such regulations are herein specifically varied or required.
2. The use and development of the property shall be in substantial conformance with the plot plan and floor plan submitted with the application and marked Exhibit "A", except as may be revised as a result of this action.
3. The authorized use shall be conducted at all times with due regard for the character of the surrounding district, and the right is reserved to the Zoning Administrator to impose additional corrective Conditions, if, in the Administrator's opinion, such Conditions are proven necessary for the protection of persons in the neighborhood or occupants of adjacent property.
4. All graffiti on the site shall be removed or painted over to match the color of the surface to which it is applied within 24 hours of its occurrence.

5. A copy of the first page of this grant and all Conditions and/or any subsequent appeal of this grant and its resultant Conditions and/or letters of clarification shall be printed on the building plans submitted to the Department of City Planning and the Department of Building and Safety for purposes of having a building permit issued at any time during the term of this grant.
6. Within 30 days of the effective date of this grant, a covenant acknowledging and agreeing to comply with all the terms and conditions established herein shall be recorded in the County Recorder's Office. The agreement (standard master covenant and agreement form CP-6770) shall run with the land and shall be binding on any subsequent owners, heirs or assigns. The agreement with the conditions attached must be submitted to the Development Services Center for approval before being recorded. After recordation, a certified copy bearing the Recorder's number and date shall be provided to the Development Services Center for inclusion in the case file.
7. **Authorization.** Authorized herein is the construction, use, and maintenance of two single-family dwellings on a hillside lot that does not have a 20-foot wide Continuous Paved Roadway from their driveway apron to the boundary of the Hillside Area, a reduced front yard setback, and a Specific Plan Compliance Review for compliance with the Mount Washington/Glassell Park Specific Plan.
 - a. A zero-foot front yard setback is authorized for the dwellings, if a dedication from the property is required in conjunction with improvements to the Cliff Drive public right-of-way.
 - b. A minimum 3-foot front yard setback is authorized for the dwellings, if no dedication from the property is required in conjunction with improvements to the Cliff Drive public right-of-way.
8. No other deviations have been requested or approved from any other applicable provisions of the Hillside regulations (Section 12.21 C.10 of the LAMC Chapter 1). All applicable provisions shall be observed.
9. Prior to the removal of any Protected Tree, a Permit and approved replacement plan shall be obtained from the Urban Forestry Division, Bureau of Street Services, Department of Public Works.
10. Prior to Development Services Center condition clearance for the issuance of a permit for construction of the dwellings, the applicant shall complete all improvements necessary to provide a minimum 20-foot wide roadway along the whole of the property frontage.
11. Prior to Development Services Center condition clearance for the issuance of a permit for construction of the dwellings, the applicant shall submit the driveway plans to the Department of Transportation for review and approval. Said Department's approval shall be included in the plans submitted to the Development Services Center.

12. Prior to Development Services Center condition clearance for the issuance of a permit for construction of the dwellings, the applicant shall submit the plans to the Fire Department for review and approval. Said Department's approval shall be included in the plans submitted to the Development Services Center.
13. The project shall comply with all conditions contained within the August 8, 2024, Department of Building and Safety, Geology and Soils Report Approval Letter, Log # 129125-02, and as it may be further amended.
14. **Retaining Walls.** Pursuant to LAMC Chapter 1, Section 12.21 C.8, a maximum of one free standing vertical or approximately vertical retaining wall may be built on any lot with a maximum height of 12 feet as measured from the top of the wall to the lower side of the adjacent ground elevation; or a maximum of two vertical or approximately vertical walls or portions of a wall may be maintained on a property if 1) the minimum horizontal distance between the two walls is three feet, 2) neither of the two walls exceed a height of 10 feet measured from the top of each wall to the lower side of the adjacent ground elevation at each wall, and 3) in no case shall the height of a wall located in a required yard exceed the height allowed by Section 12.22 C.20.(f).
15. **Stormwater Drainage System.** Replacement/installation of a stormwater drainage system shall be pursuant to issued permit(s) after review and approval by the Department of Public Works and the Department of Building and Safety.
16. **Mount Washington/Glassell Park Specific Plan Compliance Conditions.**
 - a. **Site Development** – Except as modified herein, the project shall be in substantial conformance with the plans and materials submitted by the applicant, stamped "Exhibit A", and attached to the subject case file.
 - b. **Floor Area** – As defined by the Mount Washington/Glassell Park Specific Plan, Floor Area is that area in square feet confined within the exterior walls of a building of a One-Family Project, including the area of stairways, shafts, covered automobile parking areas and basement storage areas, and excluding uncovered outdoor decks. The total gross floor area shall not exceed 3,693.83 square feet, including attached covered parking areas.
 - c. **Height** – The proposed Cliff Residence South shall be limited to 35 feet 9 inches in height and Cliff Residence North shall be limited to 29 feet 2 inches in height. Within six feet of the front lot line, the building heights for both dwellings shall be limited to 15 feet. Within six feet to 12 feet of the front lot line, the building heights for both dwellings shall be limited to 24 feet.
 - d. **Front Yard Setback** – The project shall provide a minimum front yard setback according to Condition No. 7.
 - e. **Parking** – The project shall provide vehicle parking spaces as required by the LAMC and determined by the Department of Building and Safety.

f. **Landscape Plan:**

- i. Xeriscape Requirements. The project shall comply with the xeriscape requirements set forth under Sections 12.40 through 12.43 of the LAMC.
- ii. Landform Planting Design. To the extent feasible, the type and placement of landscape materials on graded sloped shall conform to the standards set forth in the Landform Grading Manual.
- iii. Fire Safety. The landscaping and preservation, relocation, and removal of Native and Significant Trees shall not require any planting in violation of applicable fire safety regulations.
- iv. Landscape and Preservation, Relocation, and Removal of Native and Significant Trees. As identified in the Tree Report prepared by Julio Matos (WE-9101A), revised on September 16, 2025, there are three (3) Protected Trees/Shrubs and three (3) Significant Trees on-site. No on-site Protected Trees are proposed for removal. One (1) Significant Tree is proposed for removal as part of the project. There is one (1) Protected Street Tree. The one (1) Protected Street Tree is proposed for removal. The project shall provide Replacement Trees per LAMC Section 46.02. of the Code for the one (1) Protected Street Tree being removed. One (1) Replacement Tree will be planted on a 1:1 ratio for the one (1) Significant Tree being removed. This Tree Report was reviewed by the Urban Forestry Division on September 16, 2025.
- v. The applicant shall observe the Tree Protection Guidelines set forth in said tree report and the standards of approval of Relocation/Removal of Native or Significant Trees of the Mount Washington/Glassell Park Specific Plan during the Pre-Construction Phase and Construction Phase by using protective fencing, keeping the site clean, sufficient irrigation, no flooding, using hand tools around the tree locations, do not back any equipment up to the trunk of trees, avoid root impact, trenching and root pruning, maintain natural grade, place mulch, and under observation by an arborist.

17. **Construction Conditions.**

- a. **Construction Traffic Mitigation Plan**. The property owner is fully responsible and shall ensure the project contractor and crew read, fully understand, and comply with all conditions imposed in this grant and the Construction Traffic Management Plan reviewed and approved by the Los Angeles Department of Transportation on October 21, 2024, during all applicable demolition, grading and construction phrases of the project. Should this grant contain more restrictive conditions, the project personnel shall comply with the more restrictive conditions.

b. **Hillside Construction Regulations.**

- i. **Maximum Grading.** For any single lot, the total cumulative quantity of Grading, or the total combined value of both Cut and Fill for the import and export of earth, or incremental Cut and Fill for Import and Export of earth shall be limited to the “by-right” maximum pursuant to Section 12.21 C.10 and shall not exceed 6,000 cubic yards.
- ii. **Maximum Import and/or Export for Hillside Areas Fronting Substandard Streets.** For a lot which fronts onto a Substandard Hillside Limited Street, as defined in Section 12.03 of this Code, the total cumulative quantity of Import and Export of earth combined, shall be no more than 75 percent of the “by-right” maximum pursuant to Section 12.21 C.10 and shall not exceed 6,000 cubic yards.
- iii. **Hauling Truck Trips.** A maximum of four trucks are permitted to haul per hour per project site. A grouping or convoy of hauling vehicles shall not be allowed; only one hauling vehicle is permitted per project site at any one time.
- iv. **Hauling Truck Operations.** As conditions of project approval for the issuance of a grading or building permit for projects in a HCR District, each of the following hauling operation standards shall be met:
 1. Projects required to obtain a Haul Route approval from the Board of Building and Safety Commissioners for the import and/or export of 1,000 cubic yards or more of earth material shall prominently post the final action letter with the approved Haul Route staff report on the job site at all times.
 2. No grading shall be performed within any areas designated “hillside” unless a copy of the grading permit is prominently posted on the job site at all times.
 3. All hauling vehicles must be identified by a placard identifying the project address which shall be prominently displayed on each hauling vehicle.
- v. **Equipment.** As conditions of project approval for the issuance of a grading or building permit for projects in a HCR District, each of the following equipment standards shall be met:
 1. 10-wheeler dump trucks (with a 10 cubic yard capacity) or smaller are the only type of trucks permitted for hauling of earth. Notwithstanding the foregoing, the Board of Building and Safety Commissioners may authorize the use of other types of hauling vehicles for a project through the Haul Route approval process.

2. Hauling and grading equipment shall be kept in good operating condition and muffled as required by law.
- vi. **Operating Hours and Construction Activity.** Compliance with each of the following standards shall be required for all projects in a HCR District requiring the issuance of a grading or building permit. However, if a Haul Route approval by the Board of Building and Safety Commissioners is required for import and/or export of 1,000 cubic yards or more, then the conditions set by the Board of Building and Safety Commissioners during the Haul Route approval process shall prevail and the following standards shall not apply.
1. Hauling operations shall be conducted only on Monday through Friday, between the hours of 9:00 a.m. and 3:00 p.m. Hauling operations on Saturdays, Sundays, or state or federal designated holidays is strictly prohibited.
 2. Haul trucks shall be staged off-site and outside of the HCR District. As deemed necessary, the Board of Building and Safety Commissioners may permit staging on-site or in any alternate staging area by special condition during the Haul Route Approval process.
 3. Construction activity shall be limited to Monday through Friday, between the hours of 8:00 a.m. to 6:00 p.m. Exterior construction work at any other time is strictly prohibited. However, interior construction work may be conducted on Saturdays between the hours of 8:00 a.m. to 6:00 p.m. Excess exterior illumination of the site through the use of flood lights and/or similar lighting devices is strictly prohibited after 6:00 p.m. on any day of the week.
 4. A log noting the dates of hauling activity and the number of hauling truck trips per day shall be available on the job site at all times.
 5. The owner or contractor shall control dust caused by grading and hauling and provide reasonable control of dust caused or exacerbated by wind at all times. Grading and hauling activities shall be discontinued during periods of high winds and Red Flag days as determined by the Los Angeles Fire Department.
 6. Loads shall be secured by trimming and shall be covered to prevent spillage and dust. Haul trucks are to be contained at the export site to prevent blowing of dirt and are to be cleaned of loose earth at the export site to prevent spilling.

7. Streets shall be cleaned of spilled materials at the termination of each workday.
8. "Truck Crossing" warning signs shall be placed 300 feet in advance of the exit from the project site in each direction.
9. Flag person(s) shall be required for all project sites. Flag persons with radio control and warning signs shall be in compliance with the latest edition of the "Work Area Traffic Control Handbook." Flag persons provided at the job site shall assist trucks in and out of the project area.

c. **Community Notification.**

- i. 10 days prior to the commencement of grading, excavation, hauling (import and export), and construction activities, the name and telephone/cellphone number of a Construction Contact person to receive inquiries and resolve complaints from residents regarding construction activities shall be provided to all residents along Cliff Drive between its intersections with Roseview Avenue to the east and Tacoma Avenue to the south. The Construction Contact should be empowered to respond to both immediate and persistent issues.
 - ii. 10 days prior to the commencement of grading, excavation, hauling (import and export), and construction activities, the applicant shall provide a written estimated schedule to all residents along Cliff Drive between its intersections with Roseview Avenue to the east and Tacoma Avenue to the south. The schedule shall indicate the anticipated dates and times of specified activity, their anticipated duration, and specific notes about anticipated impacts to Cliff Drive. This schedule shall be updated and redistributed as necessary to reflect changes in the schedule.
 - iii. Visible and legible sign(s) (at a distance of 50 feet) shall be posted and maintained on the construction site identifying a telephone number for (1) Parking Enforcement, Department of Transportation; (2) Building and Safety enforcement; and, (3) the Construction Contact where residents can inquire about the construction process and register complaints; calls to this telephone/cellphone number shall be immediately responded to. The signs shall be located in a conspicuous place on the subject property, along Cliff Drive, and shall remain visible, legible, and attached to its post throughout the entire construction period.
- d. Complaints or inquiries to the Construction Contact shall be responded to within 24 hours or sooner to ensure resolution of a problem or violation.
- e. **Reduced Roadway Width.** Construction activities shall not reduce the Cliff Drive roadway width to less than 10 feet.

- i. Whenever construction-related activities will reduce the Cliff Drive roadway width, flag persons, equipped with working and operable two-way radios, shall coordinate traffic between the construction site and the intersections of Cliff Drive and Roseview Avenue to the east and Tacoma Avenue to the south, to facilitate pauses in the construction activity in order to allow reasonable and safe vehicle passage past the construction site.
- ii. No construction activities, including construction material/vehicle deliveries, pick-ups, soil hauling, and concrete pouring, may be conducted that reduces the Cliff Drive roadway width on trash pick-up and Red Flag days.
- iii. No vehicle belonging to project contractors, subcontractors, vendors, or laborers exceeding a width of 8 feet (including side mirrors) shall be parked along Cliff Drive at any time.
- f. No construction vehicle, contractor vehicle, subcontractor vehicle, vendor, worker vehicle, material lay down, or trash bin, shall obstruct any driveway of any property in the surrounding area.
- g. All deliveries shall be coordinated so that no more than one vendor/delivery vehicle is on Cliff Drive at any one time.
- h. Areas with signs labeled “No Parking” and “No Stopping” by LADOT shall not be used for parking and staging.
- i. Construction/Hauling Vehicle Staging. An off-site staging area for large trucks and any other construction vehicles and a construction parking plan shall be identified and utilized in order to control the frequency of construction traffic to the site and in the neighborhood to the satisfaction of the Department of Transportation. The specifics of the plan shall be printed on the plans.
 - i. No more than one truck shall be at the property at any one time. All trucking activities for deliveries during grading and construction stages shall be coordinated so that only one truck vehicle is at the site at one time; a construction supervisor shall be present at such time to prevent any potential traffic impacts.
 - ii. Staging will be done onsite to the extent feasible. No staging shall take place on any other street in the neighborhood.
 - iii. Concrete trucks shall be staged onsite to the extent feasible. When staging will need to be adjacent to the site, at no times shall adjacent driveways be blocked, nor can one lane of the street be blocked without the presence of a flagger. The applicant shall secure a street use permit from the Bureau of Street Services when necessary for

said concrete pouring. No staging shall take place on any other street in the neighborhood.

- j. During all phases of construction, all materials related to the project shall be stored on private property. No building materials shall be stored overnight within the public right-of-way.
- k. All debris, trash and waste generated by the construction, including but not limited to building material remnants, removed weeds or dirt, food or drinks consumed by workers, etc., must be removed from the site or kept in a covered, trash receptacle on the property. Any trash stored on site must be removed at least once per week, or whenever the storage receptacle is full, whichever is sooner.
- l. No flood lighting shall be utilized after 6:00 p.m.
- m. Construction activities shall be scheduled so as to avoid operating several pieces of equipment simultaneously, which causes high noise levels. The project contractor shall use power construction equipment with state-of-the-art noise shielding and muffling devices.

18. INDEMNIFICATION AND REIMBURSEMENT OF LITIGATION COSTS

Applicant shall do all of the following:

- a. Defend, indemnify and hold harmless the City from any and all actions against the City relating to or arising out of, in whole or in part, the City's processing and approval of this entitlement, including but not limited to, an action to attack, challenge, set aside, void, or otherwise modify or annul the approval of the entitlement, the environmental review of the entitlement, or the approval of subsequent permit decisions, or to claim personal property damage, including from inverse condemnation or any other constitutional claim.
- b. Reimburse the City for any and all costs incurred in defense of an action related to or arising out of, in whole or in part, the City's processing and approval of the entitlement, including but not limited to payment of all court costs and attorney's fees, costs of any judgments or awards against the City (including an award of attorney's fees), damages, and/or settlement costs.
- c. Submit an initial deposit for the City's litigation costs to the City within 10 days' notice of the City tendering defense to the Applicant and requesting a deposit. The initial deposit shall be in an amount set by the City Attorney's Office, in its sole discretion, based on the nature and scope of action, but in no event shall the initial deposit be less than \$50,000. The City's failure to notice or collect the deposit does not relieve the Applicant from responsibility to reimburse the City pursuant to the requirement in paragraph (b).

- d. Submit supplemental deposits upon notice by the City. Supplemental deposits may be required in an increased amount from the initial deposit if found necessary by the City to protect the City's interests. The City's failure to notice or collect the deposit does not relieve the Applicant from responsibility to reimburse the City pursuant to the requirement in paragraph (b).
- e. If the City determines it necessary to protect the City's interest, execute an indemnity and reimbursement agreement with the City under terms consistent with the requirements of this condition.

The City shall notify the applicant within a reasonable period of time of its receipt of any action and the City shall cooperate in the defense. If the City fails to notify the applicant of any claim, action, or proceeding in a reasonable time, or if the City fails to reasonably cooperate in the defense, the applicant shall not thereafter be responsible to defend, indemnify or hold harmless the City.

The City shall have the sole right to choose its counsel, including the City Attorney's office or outside counsel. At its sole discretion, the City may participate at its own expense in the defense of any action, but such participation shall not relieve the applicant of any obligation imposed by this condition. In the event the Applicant fails to comply with this condition, in whole or in part, the City may withdraw its defense of the action, void its approval of the entitlement, or take any other action. The City retains the right to make all decisions with respect to its representations in any legal proceeding, including its inherent right to abandon or settle litigation.

For purposes of this condition, the following definitions apply:

"City" shall be defined to include the City, its agents, officers, boards, commissions, committees, employees, and volunteers.

"Action" shall be defined to include suits, proceedings (including those held under alternative dispute resolution procedures), claims, or lawsuits. Actions include actions, as defined herein, alleging failure to comply with any federal, state or local law.

Nothing in the definitions included in this paragraph are intended to limit the rights of the City or the obligations of the Applicant otherwise created by this condition.

OBSERVANCE OF CONDITIONS - TIME LIMIT - LAPSE OF PRIVILEGES

All terms and conditions of the approval shall be fulfilled before the use may be established. The instant authorization is further conditional upon the privileges being utilized within three years after the effective date of approval and, if such privileges are not utilized or substantial physical construction work is not begun within said time and carried on diligently to completion, the authorization shall terminate and become void.

TRANSFERABILITY

This authorization runs with the land. In the event the property is to be sold, leased, rented or occupied by any person or corporation other than yourself, it is incumbent upon you to advise them regarding the conditions of this grant.

VIOLATIONS OF THESE CONDITIONS, A MISDEMEANOR

Section 13A.2.7.G. of Chapter 1A of the Los Angeles Municipal Code provides:

“A Quasi-judicial action or any conditional approval granted by the Director, pursuant to the authority of this Chapter or Chapter I. (General Provisions and Zoning) of this Code shall become effective upon utilization of any portion of the privilege, and the owner and applicant shall immediately comply with its conditions. The violation of any condition imposed by the Director, Zoning Administrator, Area Planning Commission, City Planning Commission, or City Council in connection with the granting of any action taken pursuant to the authority of this Chapter or Chapter I. (General Provisions and Zoning), shall constitute a violation of this Chapter or Chapter I. (General Provisions and Zoning) and shall be subject to the same penalties as any other violation of this Code.”

Every violation of this determination is punishable as a misdemeanor and shall be punishable by a fine of not more than \$2,500 or by imprisonment in the county jail for a period of not more than six months, or by both such fine and imprisonment.

NOTICE

The applicant is further advised that subsequent contact regarding this determination must be with the staff assigned to this case. This would include clarification, verification of condition compliance and plans or building permit applications, etc., and shall be accomplished **BY APPOINTMENT ONLY**, in order to assure that you receive service with a minimum amount of waiting. You should advise any consultant representing you of this requirement as well.

FINDINGS OF FACT

After thorough consideration of the statements contained in the application, the plans submitted therewith, and the statements made at the public hearing on February 12, 2026, all of which are by reference made a part hereof, as well as knowledge of the property and surrounding district, I find that the requirements for authorizing conditional use approvals under the provisions of Section 12.24 X.28 of Chapter 1 and Section 13B.2.1. of Chapter 1A, and Section 13B.4.2. of Chapter 1A and the Mount Washington/Glassell Park Specific Plan, Ordinance No. 168,707, have been established by the following facts:

BACKGROUND

The subject property is a hillside, southeasterly down-sloping, interior, approximately 9,326 square-foot parcel of land with an approximately 240-foot frontage on the east side

of Cliff Drive. There is an 8-foot wide sanitary sewer easement that runs from Cliff Drive for a length of approximately 60 feet along the eastern property line. The property is located on a turn in the roadway, such that Cliff Drive is located on the northern and western sides of the property. The property is vacant and undeveloped.

The property is located within the Northeast Los Angeles Community Plan and the associated General Plan Land Use Map designates the property for Low Low Density Residential land uses, with corresponding Zones of RE9, RS, R1, RU, RD6, RD5. The property is zoned R1-1-HCR. The property is further located within the Mount Washington/Glassell Park Specific Plan area (ZI-1857), Northeast Los Angeles Hillside Construction Regulation (HCR) District (ZI-2467), East Los Angeles State Enterprise Zone (ZI-2129), a Hillside Area, Very High Fire Hazard Severity Zone, 300-foot Habitat Buffer zone, an Urban Agriculture Incentive Zone, and is located approximately 2.29 kilometers from the Raymond Fault.

The proposed project is the construction of two new single-family dwellings on a hillside lot. As proposed, the project seeks a waiver of the requirements to provide a 20-foot roadway width along the property frontage and from the driveway to the boundary of the Hillside Area; relief to allow a zero-foot front yard setback in lieu of minimum 5 feet otherwise required; and a Specific Plan Project Compliance review for compliance with the Mount Washington/Glassell Park Specific Plan.

According to information submitted by the applicant:

The present use of the downslope property located at 1236 N Cliff Dr (also listed as 1236 Cliff Dr) is vacant land in the R-1 land use. The proposed use is as a single-family SB-9 Two-Unit Development (TUD) with tandem SB-9 Urban Lot Split (ULS), creating two units to be split onto their own individual parcel when the subdivision map is finalized.

The ADM case for the ULS was applied for first (see Letter of Compliance (LOC) for ADM-2024-7983-PMUL); however, the completion of the subdivision will occur within 36-months of the LOC, wherein no stipulation is given for the finalizing of the map ahead of filing the TUD's CU1s on the project site. Note that the following case filing materials, such as the plan set, have removed the ULS-specific language and notations to avoid confusion as instructed during the Geographic Referral Form City Planning initial review and screening process.

The Class 1 Conditional Use Permit (CU1) application includes the two-unit development at 1236 N Cliff Dr due to required variances under the Mount Washington Specific Plan and Baseline Hillside Ordinance. For filing purposes, the smaller unit is listed as "under future finalized SB-9," with CU1s applied to the site pre-subdivision. The larger unit ("Cliff Residence South") included in this application is 2,380.78sqf located on the existing flat portion to the south and the smaller unit ("Cliff Residence North") is 1,313.05sqf located to the north. Both units do not exceed the 45ft height requirement per the Baseline Hillside Ordinance and the approximately 3,693.83sqft combined floor area maximum per Mount Washington Glassell Park Specific Plan calculation taken from the post-dedication

lot area (3,696.43sqft). All zoning regulations and calculations are enforced pre- and post-subdivision, whichever stricter.

The lot has two side lot lines and a long frontage where N Cliff Dr curves around the gully. A former residence (built 1921, expanded 1952) was demolished in 1974 after an electrical fire. N Cliff Dr is a substandard hillside limited street, ranging 12–30 feet wide and encroaching up to 7 feet onto the property, with no legal street parking between Tacoma Ave and Roseview Ave. An 8-ft sewer easement runs along the northeast edge. A 3-ft dedication is technically required but is requested to be waived since the widened street will remain over 3 feet from the property line. The property contains one protected oak, two protected toyons, and three significant trees (>12-inch trunk), with one significant orchid tree previously removed due to poor health. Two neighboring off-site protected toyons exist: one on an abutting parcel and one in the public way; the latter will require removal for street widening. An existing stormwater drainage pipe crosses the property and must be upgraded and maintained consistent with a 2015 BOE directive following emergency repairs.

The on-site construction will occur in three general phases, with material storage, delivery staging, and worker parking accommodated on-site wherever feasible. When on-site parking is not possible, workers will shuttle from outside the hillside area. Phase 1 includes grading, limited street widening with rough paving, debris and excess earth removal, stormwater pipe replacement, and underground utility installation. This grading will create areas for later material delivery and storage. Export is limited by substandard hillside street regulations, resulting in approximately 60 cubic yards of net export (about six truckloads). Phase 2 consists of retaining walls, foundations, and similar major structural work. Phase 3 covers construction of the two residential units, followed by exterior landscaping, again with on-site storage and parking where feasible.

Sustainability measures include exceeding exterior fire-rating requirements, upgrading stormwater and public way infrastructure, reinforcing areas with failed retaining walls, widening the street where applicable, and preserving native vegetation and protected trees to support neighborhood character and natural shading.

Critical Public Infrastructure Improvements Included: The proposal upholds the necessity of improving existing public infrastructure beyond the street improvement requirement.

The development includes excavating and replacing the existing failing 80-year-old storm water pipe. This improvement would substantially benefit properties not only on N Cliff Dr but also those downslope homeowners within the water course. Hillside properties are at risk of mudslide destruction and so, the proposal includes a civil engineering plan that maintains and improves public infrastructure for all.

The development includes rebuilding a new retaining wall along the northern edge of the dedication in lieu of abandoning the existing two retaining walls currently

supporting the street. The new improved retaining wall proposed within the property are designed for the surcharging of large emergency vehicles.

Shared Burden Across Adjacent Lots: There exist three additional opportunities to improve the street given the dedicated public improvements included in this project.

The properties at 1237 N Cliff Dr, 1245 N Cliff Dr, and 3584 Tacoma Ave all neighbor the extent of street along the frontage of 1236 N Cliff Dr. These are three opportunities to improve the street further considering that this proposal includes other critical public improvements. The public improvements on Cliff Dr should not solely fall 1236 N Cliff Dr, but the various lot owners who have an equal stake in improving the neighborhood.

These three listed properties all benefit from improved storm water infrastructure. When those lots are improved, properties will eventually discharge their storm water to the improvement included in this proposal.

Functional Compliance with Street Widening Objectives. The project provides a 20ft clear paved width across the entirety of the frontage, fulfilling the safety and circulation goals of the Mobility Plan and Hillside Area regulations without relying on full street improvements.

The requirement to improve the street to 20ft outside the hillside area boundary cannot be feasibly met due to the presence of existing property fencing and structures that narrow the path to less than 20ft.

The vehicular traffic associated with the development will not adversely impact street access or circulation in the surrounding neighborhood. N Cliff Dr is not a highly trafficked street due to its short length between two higher traffic streets, Roseview Ave and Tacoma Ave, that exit the hillside area. Circulation on N Cliff Dr is therefore used primarily by the existing seven single family dwellings, whose residents primarily exit to outside the hillside area boundary via the closer egress route on Roseview Ave. Given this historic traffic flow by neighboring residents on N Cliff Dr, the development will not be materially detrimental or injurious to the adjacent property or improvements by not improving the street to 20ft outside the hillside area boundary.

Both possible paths (Roseview Ave and Tacoma Ave) of egress to outside the hillside area boundary are constricted by the existing property fencing and structures. This is the case between 3614 Roseview Ave and 3615 Roseview Ave, 3543 Tacoma Ave and 3548 Tacoma Ave, and 1224 N Cliff Dr and 1225 N Cliff Dr.

A precedent for waiving the street improvement requirement was established when relief was granted to a single-family development at 3622 Roseview Ave. This property is located closer to the downhill hillside area boundary, where the street is more critical to the neighborhood's traffic flow and less likely to be constricted by existing fencing or structures. The fact that the 3622 Roseview Ave property

has not improved the street to 20ft outside the hillside area boundary without any materially adverse impact on the surrounding neighborhood demonstrates that such relief can be granted without significant consequences. Considering this precedent, denying relief for LAMC § 12.21 C.10(i)(3) for the development at 1236 N Cliff Dr would be inconsistent, especially given that the addition of another unit at this location would not significantly increase the traffic demand on Roseview Ave, Tacoma Ave, and N Cliff Dr.

The requirement to improve the street to outside the hillside area boundary would go against the tenets of SB-9, which values housing density over objective design standards. The values to enforce street improvements to several thousand would be prohibitively expensive and implementing this requirement would require forgoing the construction of both units let alone one residence. The SB-9 housing density measure must be considered when enforcing this requirement as it constricts the construction of much needed housing.

There is no other configuration of the units' footprints and envelopes that would adhere to the zoning guidelines (set forth in the Mount Washington Glassell Park Specific Plan, Baseline Hillside Ordinance, among other LAMC stipulations) as to not trigger additional relief requests or approvals in addition to impeding structural and construction feasibility of the site's topography and geographic condition. See figures 2-1 through 2-8 in the included Action Request Narrative figure booklet.

The current perimeter frontage totals 59% of the total perimeter of the property. This is due to the highly irregular site conditions rendering the property boundary as two perpendicular side lot lines and one extensive front lot line. A 5ft front yard setback would eliminate 14% of the buildable area ($[\text{Gross Lot Area} - \{\text{Dedication} + \text{Side Lot Line Setbacks} + \text{Sewer Easement}\}] / [\text{Gross Lot Area} - \{\text{Dedication} + \text{Side Lot Line Setbacks} + \text{Sewer Easement} + \text{Front Yard Setback}\}]$), and with that a substantial portion of the existing, highly buildable flat area. Due to this diminished size and the required protection and management of the protected and significant trees, such guidelines in themselves would all physically preclude the construction of two 800sqft units as enforced in SB-9.

The development respects a 3ft dedication requirement and carefully situates both units on the property to utilize the existing flat area of the site advantageously. This avoids undue structural surcharging on the downhill residences, minimizes grading quantities, and reduces construction impact on the neighborhood by limiting haul routes. Increasing the stand off from the existing property line with additional 5ft would negatively impact neighboring properties without providing significant environmental benefits.

The larger and longer unit, Cliff Residence South, maintains a natural separation, approximately 12ft on average, from the widened street due to the site's irregular shape and topography. This demonstrates that an additional front yard setback requirement would provide minimal aesthetic or environmental benefits. Similarly, Cliff Residence North preserves a 6ft separation from the street after widening,

ensuring that the protected oak tree's canopy remains unharmed by the front yard setback requirement.

Mount Washington Glassell Park Specific Plan uniquely values significant trees (>12in trunk diameter), and the Los Angeles Municipal Code requires the protection of the tree/shrub species. Upholding the 5ft front yard setback requirement would be materially detrimental to the public welfare and against the tenets of the Specific Plan and Section 46.01 of the LAMC. Doing so would imperil one protected oak tree and require the destruction of one protected toyon tree, one significant glossy privet, and one significant cedar tree.

The current proposal for the buildings' footprints does not require the removal of the protected species. As confirmed by licensed arborist, Julio Matos (ISA CERTIFIED #WE9101A, DPR LICENSE # 124807), the proposal's extensive foundation system will be engineered and designed to minimize its impact on the root system or significantly alter the tree canopy and its drip line. The property's natural characteristics and the specific plan overlay requirements were thoughtfully incorporated into the design. The removal of the cedar tree would be detrimental to the neighborhood and undermine the project's design ethos, which prioritizes blending in with the area's natural and native flora.

Adhering to the requirement of a 5ft setback from the 3ft dedication would force the current two-unit proposal to destroy and impact the listed trees, as they would be further distanced from the street. In this scenario, two significant trees and one protected shrub would be removed requiring six trees to be replanted (four protected specimens for each protected tree or shrub removed, per LAMC 46.02(c)); one for each significant tree or shrub removed, per Mount Washington Glassell Park Specific Plan). This is in addition to the significant tree already to be removed citing poor health and its replacement one tree as well as one protected street shrub to be removed for street widening and its replacement four shrubs. In total, this scenario posits that eleven shrubs/trees would be replanted on one property. However, planting these new specimens, especially the native species, in such proximity would not promote their well-being and would only serve to satisfy the abstract mathematical calculation outlined in the planning code.

With the 3ft separation from the property line, the relief maintains the visual continuity of a typical hillside front yard. In all areas, landscaping can accommodate the width between the buildings' envelopes and the widened street dimension.

The proposal accommodates the 5ft front yard setback along two portions of the 240ft front lot line. The proposal includes two areas, one for both future lots post-lot split, where the front yard setback occurs. In total, this variance request asks for just over half the total frontage to be excluded from the 5ft front yard setback: 70ft portion for Cliff Dr South and 61ft for Cliff Dr North.

Given the nature of the extensive frontage, the variance would reflect a lot that has closer proportions of side, front, and rear setbacks to the other neighboring lots,

whereby the front line is not greater than 25% the total lot perimeter. The current frontage totals 51% of the total lot perimeter, which is substantial as there is no rear lot line.

According to the submitted plans, the property will be developed with two new single-family dwellings, in conjunction with subdivision action ADM-2024-7983-PMUL, utilizing the incentives provided by Senate Bill 9.

The North dwelling, oriented toward the north side of the property, will consist of approximately 1,329 square feet, within two stories and approximately 27 feet in height. The dwelling will observe an approximately 4-foot setback from the existing property line along the northern side of the property, fronting on Cliff Drive. If a 3-foot dedication is taken along this frontage, the dwelling will observe an approximately one-foot setback. One uncovered parking space will be provided on-site.

The South dwelling, oriented toward the southwestern side of the property, will consist of approximately 2,486 square feet, within two stories and approximately 35 feet in height. The dwelling will observe an approximately 3-foot front yard setback from the existing property line along the western side of the property, fronting on Cliff Drive. If a 3-foot dedication is taken along this frontage, the dwelling will observe an approximately zero-foot setback. A pedestrian and driveway bridge are proposed to connect the dwelling and parking areas to the public right-of-way. Two parking spaces will be provided on-site, in a tandem arrangement and partially underneath a carport.

Two new retaining walls are proposed. One new retaining wall is proposed within the eastern side yard and rear yard setback. A second new retaining wall is proposed to the east of the North dwelling, to facilitate a leveled outdoor area. There are no notations on the plans indicating the heights or lengths of span for either retaining wall. One existing retaining wall on the property, located along the northern frontage of the property, is noted as intended to be abandoned.

An Urban Forestry Joint Referral Form, reviewed by Urban Forestry on September 16, 2025, indicates that one protected Toyon will be removed due to a widening of the public right-of-way, and that a tree removal permit will be required.

A Tree Risk Assessment Qualified Report, reviewed by Urban Forestry Division, Department of Public Works, on September 16, 2025, documents the number, location, and condition of protected foliage species on the property, as well whether they are proposed for removal as a result of the project. The report identifies one protected Toyon and one non-protected but significantly-sized Bauhinia variegata for removal and replacement.

A Construction Traffic Management Plan, dated October 2024, reviewed and approved by the Department of Transportation on October 21, 2024, has been submitted.

A Department of Building and Safety/Public Works Preliminary Referral Form for Baseline Hillside Ordinance No. 181,624 and Hillside Ordinance No. 174,652, dated June 12, 2024, has been submitted, indicating that the Cliff Drive public right-of-way is 30 feet wide

and contains a roadway that is less than 20 feet wide. It also indicates that a 3-foot dedication would be required.

A Tree Disclosure Statement, dated May 29, 2024, identifying Julio Matos, ISA Certified #WE 9101A, DPR License No. 124807, as the project Tree Expert, disclosed that there is a Coastal Live Oak, Toyon, and a significantly-sized non-protected tree on the property.

A Biologist's Statement of Habitat, dated April 2, 2024, and prepared by Marcus C. England, Principal Biologist, England | Ecology, LLC, which concluded that there are no natural habitats, woodlands, or protected flora, are on the property. A locally protected Coast Live Oak and a Toyon were found to be present.

A Geology and Soils Report Approval Letter, Log # 129125-02, dated August 8, 2024, and issued by the Department of Building and Safety, has been submitted.

From the southwestern corner of the subject property on Cliff Avenue, to the intersection of Tacoma Avenue and Isabel Street, where the roadway width is 20 feet or greater, Tacoma Avenue measures approximately 1,033 feet in length. This curvilinear hillside public right-of-way is generally 30 feet wide, with a widening flare to 50 feet near the intersection of Tacoma Avenue and Isabel Street. A 20-foot-wide roadway can be accommodated within the existing public right-of-way. The existing roadway within this span is irregularly improved, with segments that may have a 20-foot-wide roadway, but is mostly improved to a roadway width of less than 20 feet. Along this span of roadway, there are 28 lots which front on Tacoma Drive. 10 of these lots are vacant. All of the lots are zoned for single-family residential use.

Surrounding properties

All of the adjoining and abutting properties are located on hillside lots zoned R1-1-HCR. The north adjoining properties, across Cliff Drive, are undeveloped and vacant lots. The east and south adjoining properties are developed with single-family dwellings. The west adjoining property is an undeveloped and vacant lot.

Streets

Cliff Drive, adjoining the property on the north and west, is a Substandard Hillside Limited Local Street, dedicated to a width of 30 feet and improved with an asphalt roadway.

Previous Cases, Affidavits, and Orders

City Planning staff, utilizing the Department's Zoning Information and Map Access System (ZIMAS) and the Planning Case Tracking System (PCTS), reviewed current and prior actions associated with the subject property and those within a 500-foot radius of the subject property and found the following:

Subject Property:

Case No. CPC-2022-6108-ZC-CA – On July 24, 2023, Ordinance No. 187,900 became effective, amending the "HCR" Hillside Construction Regulation Supplemental Use District to the zoning of the property.

Ordinance No. 181,128 – On May 3, 2010, this ordinance became effective, amending the definition “Hillside Areas” through the adoption of an amended reference map.

Case No. CPC-87-500 – On April 2, 1993, City Council passed Ordinance No. 168,707, establishing the Mount Washington/Glassell Park Specific Plan.

Ordinance No. 129,279 – On January 12, 1965, the City Council passed this Ordinance amending the definition “Hillside Areas” through the adoption of an amended reference map.

Surrounding Properties:

Case No. ZA-2022-2857-ZAD-SPP-HCA – On May 22, 2023, the Zoning Administrator denied the construction, use, and maintenance of a single-family residence on a lot fronting on a Substandard Hillside Limited Street, that is improved with an Adjacent Minimum Roadway width of less than 20 feet along Tacoma Avenue; and approved determinations to allow the construction, use, and maintenance of a single-family residence on a lot fronting on a Substandard Hillside Limited Street that does not have a 20-foot wide minimum Continuous Paved Roadway from the driveway apron to the hillside area; a zero-foot front yard setback in lieu of the minimum 5 feet required by LAMC in conjunction with a parking platform/deck; a 5-foot side yard setbacks in lieu of the 7-foot setback in conjunction with a platform/parking deck; a plane break of zero feet in lieu of the minimum required 5 feet in depth and 10 feet in length for a building that has a side wall exceeding 14 feet in height and a continuous length greater than 45 feet as otherwise required in conjunction with a new single-family dwelling; and a Project Permit Compliance Review for the construction, use, and maintenance of a new three-story, approximately 3,086 square-foot single-family home with a detached carport on an approximately 6,595 square-foot hillside lot; all on property located within the R1-1 Zone, at 3550 East Tacoma Avenue.

Case No. ZA-2012-3087(ZAA)(ZAD)(SPP) – On October 22, 2013, the Zoning Administrator approved a Determination to allow the construction, use, and maintenance of a single family dwelling fronting on a Substandard Hillside Limited Street where a minimum 20-foot wide Continuous Paved Roadway is not provided from the driveway apron to the boundary of the Hillside Area; Adjustments to allow the construction, use and maintenance of a driveway pedestrian bridge from the street edge to the entrance of a proposed single family dwelling, and a nine-foot high retaining wall to provide structure support to the driveway pedestrian bridge both within the front yard setback; and a Project Permit Compliance for the Mount Washington/Glassell Park Specific Plan (Ordinance No. 168,707), on property located within the R1-1 Zone, at 3612 East Tacoma Avenue.

Case No. ZA 2013-0668(ZAD)(ZAA)(SPP) – On July 12, 2013, the Zoning Administrator approved a Zoning Administrator's Determination to allow the construction, use and maintenance of a single-family dwelling fronting on a Substandard Hillside Limited Street where a minimum 20-foot wide Continuous

Paved Roadway is not provided from the driveway apron to the boundary of the Hillside Area; Adjustments to allow the construction, use, and maintenance of a pedestrian bridge from the street edge to the entrance of a proposed single family dwelling, a five-foot high retaining wall below street level, and a below street level retaining wall to support a driveway bridge ranging from four to seven feet in height, all within the front yard setback; and a Project Permit Compliance Review for the Mount Washington/Glassell Park Specific Plan (Ordinance No. 168,707), on property located within the R1-1 Zone, at 3556 East Tacoma Avenue.

Case No. ZA 2013-0666(ZAA)(ZAD)(SPP) – On July 12, 2013, the Zoning Administrator approved a Determination to allow the construction, use and maintenance of a single-family dwelling fronting onto a Substandard Hillside Limited Street where a minimum 20-foot-wide Continuous Paved Roadway is not provided from the driveway apron to the boundary of the Hillside area; an Adjustment to allow the construction, use and maintenance of a pedestrian bridge/stairway from the street edge to the entrance of a proposed single-family dwelling, a below street level 5-foot high retaining wall , and a below street level retaining wall level ranging in height from 4 to 9 feet to support a driveway bridge, all within the front yard setback; and a Project Permit Compliance for the Mount Washington/Glassell Park Specific Plan (Ordinance No. 168,707), on property located within the R1-1 Zone, at 3552 East Tacoma Avenue.

Case No. ZA 2009-0953(ZAA)(ZAD) – On July 7, 2010, the Zoning Administrator denied a Determination to allow the construction of a single-family dwelling on a lot fronting on a Substandard Hillside Limited Street that is improved with a roadway width of less than 20 feet, and adjustments to allow a reduced side yard of zero feet in lieu of the required 5 feet and a reduced rear yard of 5 feet in lieu of the required 15 feet; and approved a Determination to allow the construction of a single-family dwelling on a lot fronting on a street improved to a width of less than 20 feet and which does not have a minimum 20-foot wide Continuous Paved Roadway from the driveway apron to the boundary of the Hillside Area; on property located within the R1-1 Zone, at 3596 East Tacoma Avenue.

Case No. ZA 2008-0474(ZAD)(SPP) – On May 20, 2009, the Zoning Administrator approved Determinations to allow the construction, use and maintenance of a single-family dwelling fronting on a Substandard Hillside Limited Street that is improved to a roadway width of less than 20 feet and where a minimum 20-foot wide Continuous Paved Roadway is not provided from the driveway apron to the boundary of the Hillside area and a fence/wall located within the front yard to exceed the 42-inch maximum height permitted by the Municipal Code; and a Project Permit Compliance for the Mount Washington/Glassell Park Specific Plan (Ordinance No. 168,707), on property located within the R1-1 Zone, at 3625 East Tacoma Avenue.

Case No. ZA 2008-2272(ZAD) – On July 30, 2010, the Zoning Administrator approved Determinations to allow the construction of a single-family dwelling on a lot fronting on a Substandard Hillside Limited Street improved to a width of less than 20 feet and which does not have a minimum 20-foot wide Continuous Paved

Roadway from the driveway apron to the boundary of the Hillside Area, on property located within the R1-1 Zone, at 3668 East Tacoma Avenue.

Case No. ZA-2005-7090(ZAD) - On June 14, 2006, the Zoning Administrator denied a Determination to allow the construction of a single-family dwelling on a lot fronting on a Substandard Hillside Limited Street that is improved with a roadway width of less than 20 feet; and approved a Determination to allow the construction of a single-family dwelling on a lot that does not have a minimum 20-foot wide Continuous Paved Roadway from the driveway apron to the boundary of the Hillside Area; in conjunction with the construction and use of a 3,131 square-foot single-family dwelling, on property located within the R1-1 Zone, at 3616 Tacoma Avenue.

Case No. ZA-2005-1132(ZAD)(SPP) – On July 27, 2005, the Zoning Administrator approved a Determination to allow the construction of a single-family dwelling fronting a Substandard Hillside Limited Street improved to a width of less than 20 feet adjacent to the property, and approved a Specific Plan Project Permit compliance under the Mount Washington/Glassell Park Specific Plan, on property located within the R1-1 Zone, at 3622 East Tacoma Avenue.

Correspondence

Brianna MacGillivray and Andrew Keoghan – In a letter with attachments dated February 25, 2026, Ms. MacGillivray and Mr. Keoghan expressed their opposition to project and requests. Specifically, they feel that the proposed environmental Categorical Exemption does not apply to the project because of its steep topography, existing flooding conditions, proposed retaining systems, and substandard roadway access; the request to waive roadway improvements such as the roadway, curb, gutter, and sidewalk aggravates an existing hazardous condition along this portion of Cliff Drive; that the request for a zero-foot front yard setback is too inconsistent with other setbacks along Cliff Drive, creating more problems in conjunction with the narrow roadway; and that the development does not conform with the intent of the Mount Washington/Glassell Park Specific Plan because it results in overbearing structures, aggravated by challenging topography and a retaining wall, resulting in context insensitive structures, and combined with a reduced front yard setback, leads to a project design that reduces safety along Cliff Drive. The included attachments are a petition containing 22 signatures in opposition to the project requests; eight photographs of Cliff Drive and the subject property; 45 photographs of stormwater runoff on Cliff Drive, adjacent to the subject property; 7 photos of an unidentified muddy area; 24 photographs of stormwater runoff on what appears to be the downhill, east adjoining property; and 7 photographs of what appears to be the subject property, looking uphill, from the east adjoining property.

Norma Hunt-Allen – In an email dated February 25, 2026, Ms. Hunt-Allen expresses her opposition to the project, citing the increased density, fire hazard risk, and limited pedestrian access along Cliff Drive.

Patricia Winters – In an email dated February 13, 2026, Ms. Winters stated that the applicant had previously agreed to widen the adjacent roadway, and that curb and gutter improvements would further improve stormwater drainage in the immediate area.

Cynthia Gould – In an email dated February 23, 2026, Ms. Gould expresses her opposition to the project and requests, citing the project's over-sized homes on too-small lots, and the area's existing exposure to fire hazard due to existing narrow streets.

Councilmember Eunisses Hernandez, First Council District – In a letter dated February 23, 2026, the Councilmember expresses her opposition to the request for waiver of the roadway widening requirement along the property frontage, citing existing and on-going fire hazards and safety concerns resulting from substandard roadways in the hillside areas.

Thom Mayne, FAIA, founder, Morphosis Architects – In a letter dated February 19, 2026, Mr. Mayne expresses his support for the project.

Elsye Alam – In an email dated February 16, 2026, Ms. Alam expresses her support for the project.

Yael Pardess – In an email with attachments dated February 13, 2026, Ms. Pardess expresses her opposition to the project and expresses concern regarding the proposed conservation of the Deodar pine tree. Ms. Pardess opposes the proposed development of two dwellings and the waiver of roadway widening improvements, citing the existing substandard condition of the streets, the high fire hazard of the area, the difficulty with getting emergency response vehicles to the area as a result, and the need for off-street parking. Further, she asks that street improvements be required prior to construction. Ms. Pardess is concerned that the exiting Deodar Pine tree is too close to the proposed dwelling, will require extensive trimming that will endanger the health of the tree, and will not be compatible with new fire clearance requirements.

Lynda Valencia, President, Arroyo Seco Neighborhood Council – In a letter dated April 28, 2025, the Neighborhood Council expressed their support for the design of the dwellings, but opposed the requests to waive roadway widening requirement adjacent to the property and the zero-foot front yard setback. Further, they recommended that the removed Toyon be replaced at a ratio of 4:1.

PUBLIC HEARING

A Notice of Public Hearing was sent to abutting property owners and/or occupants residing near the subject site for which an application was filed with the Department of City Planning. All interested persons were invited to attend the public hearing where they could listen, ask questions or present testimony regarding the project. Interested parties were also invited to submit written comments regarding the request prior to the public hearing. A public hearing was held before the Zoning Administrator on February 12, 2026 at 9:30 a.m. Due to concerns over COVID-19, the hearing was conducted entirely telephonically. 13 individuals participated in the meeting. The purpose of the hearing was to obtain public testimony from affected and/or interested persons regarding the application.

Hallie Black, applicant, summarized the project and requests as follows:

- A presentation was shown, a copy of which has been included in the case file.
- The property is located in a single-family zone, a Very High Fire Hazard Severity Zone, and is a hillside lot.
- After dedications, the property will be approximately 8,000 square feet.
- The project complies with the Mount Washington/Glassell Park Specific Plan requirements and limitations.
- There are retaining walls along the north side of the property that support the existing Cliff Drive roadway.
- We will widen the Cliff Drive roadway adjacent to the property.
- We cannot improve all of Cliff Drive to the boundary of the hillside area.
- We are requesting a setback reduction from Cliff Drive.
- If a dedication is taken, then the setback will be zero feet; if the dedication is waived, then the setback will be 3 feet.
- There are private property improvements within the public right-of-way that prevent roadway widening.
- One Toyon tree will be removed.

In response to questions posed by the Zoning Administrator, the applicant clarified that the house design is fully compliant with zoning regulations, except for the setback; that a 20-foot wide roadway will be provided adjacent to the property – only seeking waiver or reduction of gutter, curb, sidewalk improvements; and that a zero-foot setback is requested only if a dedication will be required along Cliff Drive; if no dedication is required, then a 3-foot setback is requested.

Following this, the hearing was then opened to receive testimony from the community at-large. Given the number of participants, the Zoning Administrator limited testimony to a maximum of two minutes per commentor:

Kyle Hickley, Deputy, Council District 1

- We have concerns about the request to waive required roadway widening.
- We will submit a letter for consideration.

Yael Pardess

- I appreciate the applicant's willingness to widen the Cliff Drive roadway.
- I have concerns about the proposed two dwelling units on one lot.
- There are fire safety concerns in this area.
- Existing trees will be too close to the dwellings.
- Will four Toyon trees be required to replace the one that is removed?
- The project should be limited to one dwelling unit.

Ye Sun Yi

- I am a local resident.
- I support the project and requests.

- The applicant took my concerns under consideration.
- Cliff Drive will be widened.
- There needs to be a balance between housing, fire safety, and environmental protections.

Cooper Mayne

- I am the husband of the applicant.
- The proposed design keeps the sharp turn on Cliff Drive open.
- We worked hard for good design on the property.

Brandi Moore

- I am a local resident.
- My biggest concerns are about street widening.
- I have no issue with a lack of curbs.
- I just want to make sure that people are safe.

Elsye Alam

- I am a local resident.
- I strongly support the project.
- SB9 helps to facilitate new dwelling construction.
- The project is below the Specific Plan limitations.
- The project is compatible and respects the community.

Kimberly Calleros

- I am a local neighbor.
- I have questions about emergency access – has LAFD reviewed this project?

Brianna

- I am a local resident.
- I have concerns – I will submit a letter.
- My biggest concern is about public safety.
- 20 feet is less than the minimum safe width.
- I have reviewed many project documents – I am not certain that the project meets all requirements.
- I oppose the requests to waive pedestrian improvements.
- The project will impact the local stormwater drainage.

Joseph Schmough

- I am a frequent visitor to the neighborhood.
- SB9 is a state regulation.
- The project will be an improvement over the exiting conditions.
- I am in support of the project.

Andrew Cogen

- I am a local resident.
- I have concerns about the waiver of public improvements.
- There has been severe flooding in the neighborhood.
- Would like assurances from the applicant that no additional dwelling units will be built.

Hunter

- I am a local resident.
- There is a context to consider.
- Roadway widening is sporadic, and detracts from the neighborhood aesthetic.
- Wider roadways do not actually address traffic and drainage issues.
- The project does not improve the property.

Bob Williams

- I am a local resident.
- I did not understand the issue regarding the retaining walls.
- The roads are controlled by the county – 20-feet wide is required.
- Cliff / Tacoma Avenue is an important intersection, and is substandard.
- This will be a duplex on a single-family dwelling lot, with parking issues.
- We cannot give anything away that would cause a hazard.
- I oppose the project.

After all public testimony had been received, the applicant was given an opportunity to respond to those comments:

Hallie Black

- The Toyon tree will be replaced with 4 new plantings.
- The exterior building construction will feature double the fire rating required.
- Only two dwelling units are proposed.
- Cliff Drive, along the property frontage, will be improved with a minimum 20-foot roadway.
- All required parking will be provided on-site.

At the conclusion of the hearing, the Zoning Administrator conferred with the Council Office representative and Applicant, and agreed to take the matter under advisement until the close of the business day on February 25, 2026, in order to receive additional public comment and a letter from the Council Office.

FINDINGS

Following (highlighted) is a delineation of the findings and the application of the relevant facts to same:

1. **The project will enhance the built environment in the surrounding neighborhood or will perform a function or provide a service that is essential or beneficial to the community, city or region.**

The subject property is a hillside, southeasterly down-sloping, interior, approximately 9,326 square-foot parcel of land with an approximately 240-foot frontage on the east side of Cliff Drive. There is an 8-foot wide sanitary sewer easement that runs from Cliff Drive for a length of approximately 60 feet along the eastern property line. The property is located on a turn in the roadway, such that Cliff Drive is located on the northern and western sides of the property. The property is vacant and undeveloped.

All of the adjoining and abutting properties are located on hillside lots zoned R1-1-HCR. The north adjoining properties, across Cliff Drive, are undeveloped and vacant lots. The east and south adjoining properties are developed with single-family dwellings. The west adjoining property is an undeveloped and vacant lot.

The proposed project is the construction of two new single-family dwellings on a hillside lot. As proposed, the project seeks a waiver of the requirements to provide a 20-foot roadway width along the property frontage and from the driveway to the boundary of the Hillside Area; and relief to allow a zero-foot front yard setback in lieu of minimum 5 feet otherwise required.

According to information submitted by the applicant:

The present use of the downslope property located at 1236 N Cliff Dr (also listed as 1236 Cliff Dr) is vacant land in the R-1 land use. The proposed use is as a single-family SB-9 Two-Unit Development (TUD) with tandem SB-9 Urban Lot Split (ULS), creating two units to be split onto their own individual parcel when the subdivision map is finalized.

The Class 1 Conditional Use Permit (CU1) application includes the two-unit development at 1236 N Cliff Dr due to required variances under the Mount Washington Specific Plan and Baseline Hillside Ordinance. For filing purposes, the smaller unit is listed as "under future finalized SB-9," with CU1s applied to the site pre-subdivision. The larger unit ("Cliff Residence South") included in this application is 2,380.78sqf located on the existing flat portion to the south and the smaller unit ("Cliff Residence North") is 1,313.05sqf located to the north. Both units do not exceed the 45ft height requirement per the Baseline Hillside Ordinance and the approximately 3,693.83sqft combined floor area maximum per Mount Washington Glassell Park Specific Plan calculation taken from the post-dedication lot area (3,696.43sqft). All zoning regulations and calculations are enforced pre- and post-subdivision, whichever stricter.

Sustainability measures include exceeding exterior fire-rating requirements, upgrading stormwater and public way infrastructure, reinforcing areas with failed retaining walls, widening the street where applicable, and preserving

native vegetation and protected trees to support neighborhood character and natural shading.

Critical Public Infrastructure Improvements Included: The proposal upholds the necessity of improving existing public infrastructure beyond the street improvement requirement.

The development includes excavating and replacing the existing failing 80-year-old storm water pipe. This improvement would substantially benefit properties not only on N Cliff Dr but also those downslope homeowners within the water course. Hillside properties are at risk of mudslide destruction and so, the proposal includes a civil engineering plan that maintains and improves public infrastructure for all.

The development includes rebuilding a new retaining wall along the northern edge of the dedication in lieu of abandoning the existing two retaining walls currently supporting the street. The new improved retaining wall proposed within the property are designed for the surcharging of large emergency vehicles.

Functional Compliance with Street Widening Objectives. The project provides a 20ft clear paved width across the entirety of the frontage, fulfilling the safety and circulation goals of the Mobility Plan and Hillside Area regulations without relying on full street improvements.

There is no other configuration of the units' footprints and envelopes that would adhere to the zoning guidelines (set forth in the Mount Washington Glassell Park Specific Plan, Baseline Hillside Ordinance, among other LAMC stipulations) as to not trigger additional relief requests or approvals in addition to impeding structural and construction feasibility of the site's topography and geographic condition.

The development respects a 3ft dedication requirement and carefully situates both units on the property to utilize the existing flat area of the site advantageously. This avoids undue structural surcharging on the downhill residences, minimizes grading quantities, and reduces construction impact on the neighborhood by limiting haul routes. Increasing the stand off from the existing property line with additional 5ft would negatively impact neighboring properties without providing significant environmental benefits.

The larger and longer unit, Cliff Residence South, maintains a natural separation, approximately 12ft on average, from the widened street due to the site's irregular shape and topography. This demonstrates that an additional front yard setback requirement would provide minimal aesthetic or environmental benefits. Similarly, Cliff Residence North preserves a 6ft separation from the street after widening, ensuring that the protected oak tree's canopy remains unharmed by the front yard setback requirement.

The local City Councilmember expressed opposition to the request for waiver from the requirement to provide roadway widening improvements along the property frontage. Other community members expressed similar opposition, and further cited opposition due to the project density, setback, and design, resulting in hazardous conditions along Cliff Drive and its location in a Very High Fire Hazard Severity Zone. The local Neighborhood Council expressed support for the project, but opposed the request for waiver of the roadway widening along the property frontage and the zero-foot front yard setback.

The applicant has indicated that they will provide a 20-foot-wide roadway adjacent to the property, in compliance with LAMC Section 12.21 C.10(i)(2), but they have not withdrawn the request. As such, the request to grant relief from this requirement is denied. Had the applicant not revised their project, this request would have been denied due to the need for incremental roadway widening in this area and stated public concerns regarding the safety of vehicle and pedestrian use of the existing roadway. The applicant has further stated that they seek both a waiver of a dedication along Cliff Avenue and a waiver from improvements other than the roadway width, such as gutter, curb, sidewalk, etc. The Zoning Administrator does not have the authority to grant these requests.

From the southwestern corner of the subject property on Cliff Avenue, to the intersection of Tacoma Avenue and Isabel Street, where the roadway width is 20 feet or greater, Tacoma Avenue measures approximately 1,033 feet in length. This curvilinear hillside public right-of-way is generally 30 feet wide, with a widening flare to 50 feet near the intersection of Tacoma Avenue and Isabel Street. A 20-foot-wide roadway can be accommodated within the existing public right-of-way. The existing roadway within this span is irregularly improved, with segments that may have a 20-foot-wide roadway, but is mostly improved to a roadway width of less than 20 feet. Along this span of roadway, there are 28 lots which front on Tacoma Drive. 10 of these lots are vacant. All of the lots are zoned for single-family residential use.

The request to waive the requirement to improve the roadway to ensure that there is a minimum 20-foot-wide Continuous Paved Roadway from the property's driveway apron to the boundary of the Hillside Area has merit.

Generally, compliance with this requirement results in a disproportionate requirement to provide off-site public improvements as compared to the activities associated with the typical construction, rehabilitation, or addition to single-family dwellings, and would render an otherwise regulation-compliant development to become infeasible. Fulfilling this requirement may involve obtaining consent and dedications from other private property owners; the replacement, relocation and reconstruction of existing public and private improvements; and the construction of many hundreds of feet of public roadway. Ultimately, there is no guarantee that off-site parties would consent to any of the work necessary to meet this requirement. Failure to obtain consent may result in the applicant's inability to meet the roadway widening requirement of the Code and force the applicant to seek relief.

Individual property owners are required to provide roadway widening improvements along their property frontage in conjunction with new construction or reconstruction within the community. The applicant has stated that roadway widening improvements along the property frontage will be provided. In the long-term development and use of this community, the roadway widths will be widened.

The property is located within a well-established hillside community, located along a long and winding roadway, a significant linear distance from the boundary of the Hillside Area. Relief from this regulation has been granted in other similar projects within the surrounding neighborhood. Granting the request facilitates the construction of new dwellings and is essential and beneficial because it increases the City's total number of housing units; denying the request would result in the property remaining as a viable but vacant hillside lot.

The applicant has clarified that should a dedication be taken along Cliff Avenue, the project will require a zero-foot front yard setback; if no dedication is taken, then the project requires relief to allow a 3-foot front yard setback. It is noted that the Zoning Administrator has no discretionary authority over whether to require a dedication or easement in conjunction with the project, nor over other public improvements beyond the widening of the physical roadway.

The property has a challenging topography, with notable down-sloping from Cliff Drive. The existing Cliff Drive roadway improvements do not directly abut the subject property, and the front property line observes a significant setback from the edge of the existing roadway along Cliff Drive. As a result, the south dwelling is proposed to be accessible separately by a pedestrian and a vehicle bridge and the north dwelling will be accessible through an on-grade driveway only. In consideration of these circumstances, a reduced front yard setback will have little, if any, impact on vehicle or pedestrian safety along Cliff Drive.

Given the limited opportunities on the property on which to site a dwelling that is otherwise consistent with the underlying limitations and requirements of the Zone and Specific Plan, granting relief from the front yard setback requirement has merit, which will facilitate the construction, use, and maintenance of two new dwelling units on an otherwise vacant lot.

As such, the Zoning Administrator finds that the project will enhance the built environment in the surrounding neighborhood or will perform a function or provide a service that is essential or beneficial to the community, city or region.

2. **The project's location, size, height, operations and other significant features will be compatible with and will not adversely affect or further degrade adjacent properties, the surrounding neighborhood, or the public health, welfare and safety.**

The subject property is a hillside, southeasterly down-sloping, interior, approximately 9,326 square-foot parcel of land with an approximately 240-foot frontage on the east side of Cliff Drive. There is an 8-foot wide sanitary sewer

easement that runs from Cliff Drive for a length of approximately 60 feet along the eastern property line. The property is located on a turn in the roadway, such that Cliff Drive is located on the northern and western sides of the property. The property is vacant and undeveloped.

All of the adjoining and abutting properties are located on hillside lots zoned R1-1-HCR. The north adjoining properties, across Cliff Drive, are undeveloped and vacant lots. The east and south adjoining properties are developed with single-family dwellings. The west adjoining property is an undeveloped and vacant lot.

The proposed project is the construction of two new single-family dwellings on a hillside lot. As proposed, the project seeks a waiver of the requirements to provide a 20-foot roadway width along the property frontage and from the driveway to the boundary of the Hillside Area; and relief to allow a zero-foot front yard setback in lieu of minimum 5 feet otherwise required.

According to information submitted by the applicant:

The present use of the downslope property located at 1236 N Cliff Dr (also listed as 1236 Cliff Dr) is vacant land in the R-1 land use. The proposed use is as a single-family SB-9 Two-Unit Development (TUD) with tandem SB-9 Urban Lot Split (ULS), creating two units to be split onto their own individual parcel when the subdivision map is finalized.

The Class 1 Conditional Use Permit (CU1) application includes the two-unit development at 1236 N Cliff Dr due to required variances under the Mount Washington Specific Plan and Baseline Hillside Ordinance. For filing purposes, the smaller unit is listed as “under future finalized SB-9,” with CU1s applied to the site pre-subdivision. The larger unit (“Cliff Residence South”) included in this application is 2,380.78sqf located on the existing flat portion to the south and the smaller unit (“Cliff Residence North”) is 1,313.05sqf located to the north. Both units do not exceed the 45ft height requirement per the Baseline Hillside Ordinance and the approximately 3,693.83sqft combined floor area maximum per Mount Washington Glassell Park Specific Plan calculation taken from the post-dedication lot area (3,696.43sqft). All zoning regulations and calculations are enforced pre- and post-subdivision, whichever stricter.

The lot has two side lot lines and a long frontage where N Cliff Dr curves around the gully. A former residence (built 1921, expanded 1952) was demolished in 1974 after an electrical fire. N Cliff Dr is a substandard hillside limited street, ranging 12–30 feet wide and encroaching up to 7 feet onto the property, with no legal street parking between Tacoma Ave and Roseview Ave. An 8-ft sewer easement runs along the northeast edge. A 3-ft dedication is technically required but is requested to be waived since the widened street will remain over 3 feet from the property line. The property contains one protected oak, two protected toyons, and three significant trees (>12-inch trunk), with one significant orchid tree previously removed

due to poor health. Two neighboring off-site protected toyons exist: one on an abutting parcel and one in the public way; the latter will require removal for street widening. An existing stormwater drainage pipe crosses the property and must be upgraded and maintained consistent with a 2015 BOE directive following emergency repairs.

The on-site construction will occur in three general phases, with material storage, delivery staging, and worker parking accommodated on-site wherever feasible. When on-site parking is not possible, workers will shuttle from outside the hillside area. Phase 1 includes grading, limited street widening with rough paving, debris and excess earth removal, stormwater pipe replacement, and underground utility installation. This grading will create areas for later material delivery and storage. Export is limited by substandard hillside street regulations, resulting in approximately 60 cubic yards of net export (about six truckloads). Phase 2 consists of retaining walls, foundations, and similar major structural work. Phase 3 covers construction of the two residential units, followed by exterior landscaping, again with on-site storage and parking where feasible.

Sustainability measures include exceeding exterior fire-rating requirements, upgrading stormwater and public way infrastructure, reinforcing areas with failed retaining walls, widening the street where applicable, and preserving native vegetation and protected trees to support neighborhood character and natural shading.

The development includes excavating and replacing the existing failing 80-year-old storm water pipe. This improvement would substantially benefit properties not only on N Cliff Dr but also those downslope homeowners within the water course. Hillside properties are at risk of mudslide destruction and so, the proposal includes a civil engineering plan that maintains and improves public infrastructure for all.

The development includes rebuilding a new retaining wall along the northern edge of the dedication in lieu of abandoning the existing two retaining walls currently supporting the street. The new improved retaining wall proposed within the property are designed for the surcharging of large emergency vehicles.

The current proposal for the buildings' footprints does not require the removal of the protected species. As confirmed by licensed arborist, Julio Matos (ISA CERTIFIED #WE9101A, DPR LICENSE # 124807), the proposal's extensive foundation system will be engineered and designed to minimize its impact on the root system or significantly alter the tree canopy and its drip line. The property's natural characteristics and the specific plan overlay requirements were thoughtfully incorporated into the design. The removal of the cedar tree would be detrimental to the neighborhood and undermine the project's design ethos, which prioritizes blending in with the area's natural and native flora.

Adhering to the requirement of a 5ft setback from the 3ft dedication would force the current two-unit proposal to destroy and impact the listed trees, as they would be further distanced from the street. In this scenario, two significant trees and one protected shrub would be removed requiring six trees to be replanted (four protected specimens for each protected tree or shrub removed, per LAMC 46.02(c)); one for each significant tree or shrub removed, per Mount Washington Glassell Park Specific Plan). This is in addition to the significant tree already to be removed citing poor health and its replacement one tree as well as one protected street shrub to be removed for street widening and its replacement four shrubs. In total, this scenario posits that eleven shrubs/trees would be replanted on one property. However, planting these new specimens, especially the native species, in such proximity would not promote their well-being and would only serve to satisfy the abstract mathematical calculation outlined in the planning code.

With the 3ft separation from the property line, the relief maintains the visual continuity of a typical hillside front yard. In all areas, landscaping can accommodate the width between the buildings' envelopes and the widened street dimension.

The proposal accommodates the 5ft front yard setback along two portions of the 240ft front lot line. The proposal includes two areas, one for both future lots post-lot split, where the front yard setback occurs. In total, this variance request asks for just over half the total frontage to be excluded from the 5ft front yard setback: 70ft portion for Cliff Dr South and 61ft for Cliff Dr North.

Given the nature of the extensive frontage, the variance would reflect a lot that has closer proportions of side, front, and rear setbacks to the other neighboring lots, whereby the front line is not greater than 25% the total lot perimeter. The current frontage totals 51% of the total lot perimeter, which is substantial as there is no rear lot line.

According to the submitted plans, the property will be developed with two new single-family dwellings, in conjunction with subdivision action ADM-2024-7983-PMUL, utilizing the incentives provided by Senate Bill 9.

The North dwelling, oriented toward the north side of the property, will consist of approximately 1,329 square feet, within two stories and approximately 27 feet in height. The dwelling will observe an approximately 4-foot setback from the existing property line along the northern side of the property, fronting on Cliff Drive. If a 3-foot dedication is taken along this frontage, the dwelling will observe an approximately one-foot setback. One uncovered parking space will be provided on-site.

The South dwelling, oriented toward the southwestern side of the property, will consist of approximately 2,486 square feet, within two stories and approximately

35 feet in height. The dwelling will observe an approximately 3-foot front yard setback from the existing property line along the western side of the property, fronting on Cliff Drive. If a 3-foot dedication is taken along this frontage, the dwelling will observe an approximately zero-foot setback. A pedestrian and driveway bridge are proposed to connect the dwelling and parking areas to the public right-of-way. Two parking spaces will be provided on-site, in a tandem arrangement and partially underneath a carport.

Two new retaining walls are proposed. One new retaining wall is proposed within the eastern side yard and rear yard setback. A second new retaining wall is proposed to the east of the North dwelling, to facilitate a leveled outdoor area. There are no notations on the plans indicating the heights or lengths of span for either retaining wall. One existing retaining wall on the property, located along the northern frontage of the property, is noted as intended to be abandoned.

An Urban Forestry Joint Referral Form, reviewed by Urban Forestry on September 16, 2025, indicates that one protected Toyon will be removed due to a widening of the public right-of-way, and that a tree removal permit will be required.

A Tree Risk Assessment Qualified Report, reviewed by Urban Forestry Division, Department of Public Works, on September 16, 2025, documents the number, location, and condition of protected foliage species on the property, as well whether they are proposed for removal as a result of the project. The report identifies one protected Toyon and one non-protected but significantly-sized *Bauhinia variegata* for removal and replacement.

A Construction Traffic Management Plan, dated October 2024, reviewed and approved by the Department of Transportation on October 21, 2024, has been submitted.

A Department of Building and Safety/Public Works Preliminary Referral Form for Baseline Hillside Ordinance No. 181,624 and Hillside Ordinance No. 174,652, dated June 12, 2024, has been submitted, indicating that the Cliff Drive public right-of-way is 30 feet wide and contains a roadway that is less than 20 feet wide. It also indicates that a 3-foot dedication would be required.

A Tree Disclosure Statement, dated May 29, 2024, identifying Julio Matos, ISA Certified #WE 9101A, DPR License No. 124807, as the project Tree Expert, disclosed that there is a Coastal Live Oak, Toyon, and a significantly-sized non-protected tree on the property.

A Biologist's Statement of Habitat, dated April 2, 2024, and prepared by Marcus C. England, Principal Biologist, England | Ecology, LLC, which concluded that there are no natural habitats, woodlands, or protected flora, are on the property. A locally protected Coast Live Oak and a Toyon were found to be present.

A Geology and Soils Report Approval Letter, Log # 129125-02, dated August 8, 2024, and issued by the Department of Building and Safety, has been submitted.

The local City Councilmember expressed opposition to the request for waiver from the requirement to provide roadway widening improvements along the property frontage. Other community members expressed similar opposition, and further cited opposition due to the project density, setback, and design, resulting in hazardous conditions along Cliff Drive and its location in a Very High Fire Hazard Severity Zone. The local Neighborhood Council expressed support for the project, but opposed the request for waiver of the roadway widening along the property frontage and the zero-foot front yard setback.

The applicant has indicated that they will provide a 20-foot-wide roadway adjacent to the property, in compliance with LAMC Section 12.21 C.10(i)(2), but they have not withdrawn the request. As such, the request to grant relief from this requirement is denied. Had the applicant not revised their project, this request would have been denied due to the need for incremental roadway widening in this area and stated public concerns regarding the safety of vehicle and pedestrian use of the existing roadway. The applicant has stated that they seek both a waiver of a dedication along Cliff Avenue and a waiver from improvements other than the roadway width, such as gutter, curb, sidewalk, etc. The Zoning Administrator does not have the authority to grant these requests.

The applicant's request to waive the requirement to widen the existing roadway such that there would be a minimum 20-foot-wide Continuous Paved Roadway from the driveway apron to the boundary of the Hillside Area has merit.

From the southwestern corner of the subject property on Cliff Avenue, to the intersection of Tacoma Avenue and Isabel Street, where the roadway width is 20 feet or greater, Tacoma Avenue measures approximately 1,033 feet in length. This curvilinear hillside public right-of-way is generally 30 feet wide, with a widening flare to 50 feet near the intersection of Tacoma Avenue and Isabel Street. A 20-foot-wide roadway can be accommodated within the existing public right-of-way. The existing roadway within this span is irregularly improved, with segments that may have a 20-foot-wide roadway, but is mostly improved to a roadway width of less than 20 feet. Along this span of roadway, there are 28 lots which front on Tacoma Drive. 10 of these lots are vacant. All of the lots are zoned for single-family residential use.

The property is located within a well-established hillside community, located along a long and winding roadway, a significant linear distance from the boundary of the Hillside Area. Placing the burden of this significant public improvement on the applicant would be disproportionate to the scope of the project. Compliance with the requirement would also require the consent and cooperation of all affected off-site property owners who may not authorize necessary replacement, relocation, and reconstruction of affected private improvements. If any one of the affected property owners fails to provide consent, the applicant would not be able to comply with the requirement and then would need to seek relief due to those circumstances.

The applicant's request to allow relief from the otherwise required minimum 5-foot front yard setback has merit. The property is located along a significant bend in the roadway, which negates any attempt to preserve a sense of similar or consistent front yard setback along Cliff Drive. Due to the local topography, the setback provides no meaningful buffer from the outer edge of public improvements along Cliff Drive to the front of the proposed development. Further, the proposed reduced setback is limited in span, and will not apply to the entirety of the front yard. Strictly enforcing the setback would relocate the proposed dwellings farther downhill, jeopardizing the project's ability to meet other zoning and Specific Plan limitations for development on the property.

Granting these requests will allow the improvement of the property with a project that is otherwise in compliant with the limitations and requirements of the underlying Zoning and Specific Plan, thereby adding additional housing unit to the citywide housing stock.

It is acknowledged that any new construction of dwelling units would result in some roadway impacts during construction, and the City has an obligation to allow reasonable use of the vacant property. All hillside communities that possess narrow roads are impacted in some degree by construction activity. The most common impacts are related to construction noise, traffic, travel lane obstructions, and parking. Construction in hillside areas and concerns about these short-term impacts are common in the City. While occasional impacts can be unavoidable, they can be minimized through clear communication with the affected community and on-site coordination.

The applicant has submitted a Construction Traffic Management Plan, approved by the Department of Transportation. Further, the project will be subject to the limitations and requirements of the Northeast Los Angeles Hillside Construction Regulation District. Additional conditions have been tailored and adopted to address concerns that are unique to this project and immediate surroundings. Further, the applicant has been required to complete roadway widening improvements prior to commencement of construction of the project to allow for wider roadway conditions during construction and ensure the benefit of a wider roadway to the community. Compliance with these conditions will minimize the impacts that construction activities have on the community.

As such, the Zoning Administrator finds that, as conditioned, the project's location, size, height, operations and other significant features will be compatible with and will not adversely affect or further degrade adjacent properties, the surrounding neighborhood, or the public health, welfare and safety.

3. **The project substantially conforms to the purpose, intent and provisions of the General Plan, the applicable community plan, and any specific plan.**

The proposed project is the construction of two new single-family dwellings on a hillside lot. As proposed, the project seeks a waiver of the requirements to provide a 20-foot roadway width along the property frontage and from the driveway to the

boundary of the Hillside Area; and relief to allow a zero-foot front yard setback in lieu of minimum 5 feet otherwise required.

The General Plan is the City's roadmap for future growth and development. The General Plan Elements establish goals, policies, purposes, and programs that provide for the regulatory environment in managing the City, and for addressing environmental concerns and problems. The majority of the policies derived from these elements are implemented in the form of Municipal Code requirements. The General Plan is comprised of the Framework Element, seven state-mandated elements, and four additional elements. The Framework Element establishes the broad overall policy and direction for the General Plan.

The Land Use Element of the City's General Plan divides the City into 34 Community Plans. The subject property is located within the Northeast Los Angeles Community Plan area. The associated General Plan Land Use Map designates the property for Low Low Density Residential land uses, with corresponding zones of RE9, RS, R1, RU, RD6, RD5. The property is zoned R1-1-HCR. The property's zoning is thus consistent with the General Plan's land use designation for the site.

The Northeast Los Angeles Community Plan is silent with regards to roadway widening and setbacks. In such cases, the Zoning Administrator must interpret the intent of the Plans. Specifically, the project addresses the following goals and policies of the Community Plan:

Goal 1 A Safe, Secure, and Attractive Residential Environment for All Economic, Age, and Ethnic Segments of the Community.

Objective 1-1 To preserve and enhance existing residential neighborhoods.

Policy 1-1.1 Protect existing stable single-family and other lower density residential neighborhoods from encroachment by higher density residential and other uses that are incompatible as to scale and character or would otherwise diminish the quality of life.

Objective 1-2 To allocate land for new housing to accommodate a growth of population that is consistent with and promotes the health, safety, welfare, convenience, and pleasant environment of those who live and work in the community based on adequate infrastructure and government services, especially schools.

Policy 1-2.1 Designate specific areas to provide for adequate residential development to accommodate anticipated increases in

population while maintaining a balance between single-family and multiple-family uses.

Objective 1-3 To preserve and enhance the residential character and scale of existing single- and multi-family neighborhoods.

Policy 1-3.1 Protect the quality and scale of the residential environment through attention to the appearance of new construction including site planning and compatible building design.

Objective 1-5 To limit the intensity and density of development in hillside areas.

Policy 1-5.4 Require that any proposed development be designed to enhance and be compatible with adjacent development.

Goal 9 Adequate Community Protection Through a Comprehensive Fire and Life Safety Program.

Objective 9-1 Ensure that fire facilities and protective services are sufficient for the existing and future population and land uses.

Policy 9-1.1 Promote land use policies that enhance accessibility for fire fighting equipment and are compatible with effective levels of service.

Goal 10 To the Extent Feasible and Consistent with the Mobility Plan 2035's and Community Plans' Policies Promoting Multimodal Transportation and Safety, a System of Freeways and Streets that Provides a Circulation System Which Supports Existing, Approved, and Planned Land Uses While Maintaining a Desired Level of Service at Intersections.

Objective 10-1 To the extent feasible and consistent with the Mobility Plan 2035's and the Community Plans' policies promoting multi-modal transportation and safety, comply with Citywide performance standards for acceptable levels of service and ensure that necessary road access and street improvements are provided to accommodate traffic generated by new development.

Policy 10-1.2 Design new development projects to minimize disturbance to existing traffic flow with proper ingress and egress to parking.

The applicant has indicated that they will provide a 20-foot-wide roadway adjacent to the property, in compliance with LAMC Section 12.21 C.10(i)(2), but they have not withdrawn the request. As such, the request to grant relief from this requirement is denied. Had the applicant not revised their project, this request would have been denied due to the need for incremental roadway widening in this area and stated public concerns regarding the safety of vehicle and pedestrian use of the existing roadway.

The project's proposed two new dwelling units are consistent with the anticipated land use for the property. The proposed dwellings are consistent with the requirements and limitations of the underlying R1 Zoning of the property, except as requested. The project does not maximize the allowed square-footage or height for development on the property and is of a scale that is compatible with the surrounding single-family dwellings in the area. Together, the project demonstrates conformance with Policies 1-1.1, 1-3.1, and 1-5.4.

Development of the project will result in an improvement of the adjoining Cliff Drive roadway. The roadway widening will be an incremental improvement of the overall Cliff Drive public right-of-way, and will result in a measure of increased accessibility for emergency response services, in conformance with Policy 9-1.1.

Roadway widening improvements of the adjoining public roadway will be required prior to commencement of construction of the new dwellings. As a result, traffic along Cliff Drive will be less impacted by construction activity associated with the new dwellings, and vehicle ingress and egress from the new dwellings will similarly benefit from the wider public roadway. Finally, the project driveway plans will be required to be reviewed and approved by the Department of Transportation to ensure that their location does not result in safety issues affecting traffic along this roadway. As a result, the project is in conformance with Policy 10-1.2.

The property is further located within the Mount Washington/Glassell Park Specific Plan area. The project does not propose any deviation from the requirements or limitations of the Specific Plan.

Therefore, as conditioned, the project substantially conforms to the purpose, intent and provisions of the General Plan, the applicable community plan, and any specific plan.

4. **The request is in conformity with the public necessity, convenience, general welfare and good zoning practice.**

The proposed project is the construction of two new single-family dwellings on a hillside lot. As proposed, the project seeks a waiver of the requirements to provide a 20-foot roadway width along the property frontage and from the driveway to the boundary of the Hillside Area; and relief to allow a zero-foot front yard setback in lieu of minimum 5 feet otherwise required.

The applicant has indicated that they will provide a 20-foot-wide roadway adjacent to the property, in compliance with LAMC Section 12.21 C.10(i)(2), but they have

not withdrawn the request. As such, the request to grant relief from this requirement is denied. Had the applicant not revised their project, this request would have been denied due to the need for incremental roadway widening in this area and stated public concerns regarding the safety of vehicle and pedestrian use of the existing roadway. The applicant has stated that they seek both a waiver of a dedication along Cliff Avenue and a waiver from improvements other than the roadway width, such as gutter, curb, sidewalk, etc. The Zoning Administrator does not have the authority to grant these requests.

Granting the request for relief from the requirement to provide a minimum 20-foot-wide Continuous Paved Roadway from the driveway apron to the boundary of the Hillside Area facilitates the development of two new single-family dwellings. Strict enforcement of the requirement would burden the applicant with a disproportionate public improvement cost as compared to the scope of the project. Further, other similar projects in the area have been granted relief from this requirement.

Due to the curvilinear hillside street pattern and the changing topography, a consistent front yard setback does not provide any meaningful sense of developmental consistency within the pattern of development along this street. Granting relief from the front yard setback requirement allows for a development that is more compatible with the surrounding area. The relief is requested due to the steep topography of the lot. Strictly observing the setback would result in taller development and the removal of more trees, resulting in development that would be less compatible than the requested deviation.

Granting the requests will allow the development of the property with new dwellings, resulting in an incremental increase in the City's housing supply. Denying the requests would result in the development of any residential use upon the property as financially infeasible and/or a more negatively impactful dwelling design. As a result, the requests are in conformity with the public necessity, convenience, general welfare and good zoning practice.

Additional Roadway Findings

5. **The vehicular traffic associated with the building or structure will not create an adverse impact on street access or circulation in the surrounding neighborhood.**

The proposed project is the construction of two new single-family dwellings on a hillside lot. As proposed, the project seeks a waiver of the requirements to provide a 20-foot roadway width along the property frontage and from the driveway to the boundary of the Hillside Area.

The applicant has indicated that they will provide a 20-foot-wide roadway adjacent to the property, in compliance with LAMC Section 12.21 C.10(i)(2), but they have not withdrawn the request. As such, the request to grant relief from this requirement is denied. Had the applicant not revised their project, this request would have been denied due to the need for incremental roadway widening in this

area and stated public concerns regarding the safety of vehicle and pedestrian use of the existing roadway. The applicant has stated that they seek both a waiver of a dedication along Cliff Avenue and a waiver from improvements other than the roadway width, such as gutter, curb, sidewalk, etc. The Zoning Administrator does not have the authority to grant these requests.

A Construction Traffic Management Plan, dated October 2024, reviewed and approved by the Department of Transportation on October 21, 2024, has been submitted.

Vehicular traffic associated with the new dwellings are anticipated to be consistent with the intended use of the local street network.

The Northeast Los Angeles Community Plan designates the property for use and development with single-family dwelling uses. The project proposes a use that is consistent with that land use designation. The adjoining Cliff Drive roadway will be improved to a width of 20 feet along the property frontage. This roadway widening improvement will be required prior to the commencement of construction activities associated with the dwellings. In doing so, short-term construction activities will be less impactful along the roadway. During project construction, the applicant will be required to adhere to an approved Construction Traffic Management Plan, regulations of the Hillside Construction Regulation District, and additional construction-related conditions tailored to the immediate neighborhood. Use and maintenance of the new dwelling will have no significant adverse impact on the roadway. The project will provide all required parking on-site. Therefore, as conditioned, the vehicular traffic associated with the building or structure will not create an adverse impact on street access or circulation in the surrounding neighborhood

6. The building or structure will not be materially detrimental or injurious to the adjacent property or improvements.

The proposed project is the construction of two new single-family dwellings on a hillside lot. As proposed, the project seeks a waiver of the requirements to provide a 20-foot roadway width along the property frontage and from the driveway to the boundary of the Hillside Area.

The applicant has indicated that they will provide a 20-foot-wide roadway adjacent to the property, in compliance with LAMC Section 12.21 C.10(i)(2), but they have not withdrawn the request. As such, the request to grant relief from this requirement is denied. Had the applicant not revised their project, this request would have been denied due to the need for incremental roadway widening in this area and stated public concerns regarding the safety of vehicle and pedestrian use of the existing roadway. The applicant has stated that they seek both a waiver of a dedication along Cliff Avenue and a waiver from improvements other than the roadway width, such as gutter, curb, sidewalk, etc. The Zoning Administrator does not have the authority to grant these requests.

A Geology and Soils Report Approval Letter, Log # 129125-02, dated August 8, 2024, and issued by the Department of Building and Safety, has been submitted.

Except for the requested waiver of off-site roadway widening improvements and a reduced front yard setback, the project is otherwise compliant with the requirements and limitations for development within the underlying R1 Zone, on a hillside lot, and the Specific Plan. The dwellings will be constructed in accordance with contemporary Building and Fire Codes, in addition to other State and Federal regulations. In addition, the applicant has volunteered that an existing stormwater drainage system will be replaced, improving stormwater drainage from Cliff Drive. Taken as a whole, and as conditioned, the Zoning Administrator finds that the buildings and structures will not be materially detrimental or injurious to the adjacent property or improvements.

7. The Building or Structure will not have a materially adverse safety impact on the surrounding neighborhood.

The proposed project is the construction of two new single-family dwellings on a hillside lot. As proposed, the project seeks a waiver of the requirements to provide a 20-foot roadway width along the property frontage and from the driveway to the boundary of the Hillside Area.

The applicant has indicated that they will provide a 20-foot-wide roadway adjacent to the property, in compliance with LAMC Section 12.21 C.10(i)(2), but they have not withdrawn the request. As such, the request to grant relief from this requirement is denied. Had the applicant not revised their project, this request would have been denied due to the need for incremental roadway widening in this area and stated public concerns regarding the safety of vehicle and pedestrian use of the existing roadway. The applicant has stated that they seek both a waiver of a dedication along Cliff Avenue and a waiver from improvements other than the roadway width, such as gutter, curb, sidewalk, etc. The Zoning Administrator does not have the authority to grant these requests.

A Geology and Soils Report Approval Letter, Log # 129125-02, dated August 8, 2024, and issued by the Department of Building and Safety, has been submitted.

Granting a waiver of the requirement to widen the roadway from the project driveway apron to the boundary of the Hillside Area will not be materially detrimental or injurious to the adjacent property or improvements and will not have a materially adverse safety impact on the surrounding neighborhood.

Strict enforcement of this requirement would result in the relocation of multiple public utility poles, existing driveway aprons, and other existing public and private improvements both within the public right-of-way and upon private property, and may require the property owner to acquire additional private property in order to the accomplish the widening. These activities would result in significantly more impacts, for a greater duration of time, on affected properties.

Granting the request to waive roadway widening improvements from the project's driveway apron to the boundary of the Hillside Area results in fewer potential impacts resulting from longer construction impacts on the street itself, as well as the unintended consequences resulting from having to negotiate with affected property owners and the relocation and reconstruction of existing public and private improvements.

Except for the requested waiver of off-site roadway widening improvements and a reduced front yard setback, the project is otherwise compliant with the requirements and limitations for development within the underlying R1 Zone, on a hillside lot, and the Specific Plan. The dwellings will be constructed in accordance with contemporary Building and Fire Codes, in addition to other State and Federal regulations. The applicant has volunteered that the dwelling exteriors will be clad with fire resistant materials that exceed minimum requirements. The Cliff Drive roadway, along the property frontage, will be widened to a minimum width of 20 feet. Roadway widening will be required prior to commencement of construction activities associated with the dwellings in order to minimize impacts to Cliff Drive as a result of those activities. In addition, the applicant has volunteered that an existing stormwater drainage system will be replaced, improving stormwater drainage from Cliff Drive. Therefore, as conditioned, the Buildings and Structures will not have a materially adverse safety impact on the surrounding neighborhood.

8. The site and/or existing improvements make strict adherence to Section 12.21-C,10(i) of Chapter 1 impractical or infeasible.

The proposed project is the construction of two new single-family dwellings on a hillside lot. As proposed, the project seeks a waiver of the requirements to provide a 20-foot roadway width along the property frontage and from the driveway to the boundary of the Hillside Area.

The applicant has indicated that they will provide a 20-foot-wide roadway adjacent to the property, in compliance with LAMC Section 12.21 C.10(i)(2), but they have not withdrawn the request. As such, the request to grant relief from this requirement is denied. Had the applicant not revised their project, this request would have been denied due to the need for incremental roadway widening in this area and stated public concerns regarding the safety of vehicle and pedestrian use of the existing roadway. The applicant has stated that they seek both a waiver of a dedication along Cliff Avenue and a waiver from improvements other than the roadway width, such as gutter, curb, sidewalk, etc. The Zoning Administrator does not have the authority to grant these requests.

Other projects in the area have been granted relief from off-site roadway widening requirements to the boundary of the Hillside Area.

From the southwestern corner of the subject property on Cliff Avenue, to the intersection of Tacoma Avenue and Isabel Street, where the roadway width is 20 feet or greater, Tacoma Avenue measures approximately 1,033 feet in length. This curvilinear hillside public right-of-way is generally 30 feet wide, with a widening

flare to 50 feet near the intersection of Tacoma Avenue and Isabel Street. A 20-foot-wide roadway can be accommodated within the existing public right-of-way. The existing roadway within this span is irregularly improved, with segments that may have a 20-foot-wide roadway, but is mostly improved to a roadway width of less than 20 feet. Along this span of roadway, there are 28 lots which front on Tacoma Drive. 10 of these lots are vacant. All of the lots are zoned for single-family residential use.

Strict adherence to the requirement to ensure a 20-foot wide Continuous Paved Roadway from the project's driveway apron to the boundary of the Hillside Area is impractical and infeasible. Compliance would necessitate securing the compliance and consent of all affected property owners between the subject property and the Hillside Area boundary. The participation of the other property owners is necessary in order for the applicant to obtain necessary dedications or easements, relocate and replace affected existing private improvements such as driveways, retaining walls, and fences, and relocate and replace affected public infrastructure such as public utility poles. The financial costs of such an endeavor would quickly render the project infeasible. Further, if any individual affected private property owner declines to facilitate the roadway widening effort, the Applicant would not be able to comply with the requirement, they would need to seek this relief. To require the applicant to provide these substantial off-site improvements to the public right-of-way would be disproportionate to the scope of the project and its impact on the existing roadway infrastructure. For these reasons, the site and/or existing improvements make strict adherence to Section 12.21-C,10(i) of Chapter 1 impractical or infeasible.

Additional Setback Finding

9. The reduction in yards will not be materially detrimental to the public welfare or injurious to the adjacent property or improvements.

The proposed project is the construction of two new single-family dwellings on a hillside lot. As proposed, the project seeks relief to allow a zero-foot front yard setback in lieu of minimum 5 feet otherwise required.

According to information submitted by the applicant:

The current perimeter frontage totals 59% of the total perimeter of the property. This is due to the highly irregular site conditions rendering the property boundary as two perpendicular side lot lines and one extensive front lot line. A 5ft front yard setback would eliminate 14% of the buildable area (
$$\frac{[\text{Gross Lot Area} - \{\text{Dedication} + \text{Side Lot Line Setbacks} + \text{Sewer Easement}\}]}{[\text{Gross Lot Area} - \{\text{Dedication} + \text{Side Lot Line Setbacks} + \text{Sewer Easement} + \text{Front Yard Setback}\}]}$$
), and with that a substantial portion of the existing, highly buildable flat area. Due to this diminished size and the required protection and management of the protected and significant trees, such guidelines in themselves would all physically preclude the construction of two 800sqft units as enforced in SB-9.

The development respects a 3ft dedication requirement and carefully situates both units on the property to utilize the existing flat area of the site advantageously. This avoids undue structural surcharging on the downhill residences, minimizes grading quantities, and reduces construction impact on the neighborhood by limiting haul routes. Increasing the stand off from the existing property line with additional 5ft would negatively impact neighboring properties without providing significant environmental benefits.

The larger and longer unit, Cliff Residence South, maintains a natural separation, approximately 12ft on average, from the widened street due to the site's irregular shape and topography. This demonstrates that an additional front yard setback requirement would provide minimal aesthetic or environmental benefits. Similarly, Cliff Residence North preserves a 6ft separation from the street after widening, ensuring that the protected oak tree's canopy remains unharmed by the front yard setback requirement.

The applicant has clarified that should a dedication be taken along Cliff Avenue, the project will require a zero-foot front yard setback; if no dedication is taken, then the project requires relief to allow a 3-foot front yard setback. It is noted that the Zoning Administrator has no authority to waive a dedication requirement.

The applicant's request to allow relief from the otherwise required minimum 5-foot front yard setback has merit. The property is located along a significant bend in the roadway, which negates any attempt to preserve a sense of similar or consistent front yard setback along Cliff Drive. Due to the local topography, the setback provides no meaningful buffer from the outer edge of public improvements along Cliff Drive to the front of the proposed development. Further, the proposed reduced setback is limited in span, and will not apply to the entirety of the front yard. Strictly enforcing the setback would relocate the proposed dwellings farther downhill, jeopardizing the project's ability to meet other zoning and Specific Plan limitations for development on the property.

Despite observing a reduced front yard setback, the project contains no element that projects into the public right-of-way and proposes no use that would be in conflict with use of the roadway. Should the project be required to provide a gutter, curb, and sidewalk, these improvements would buffer the roadway from the front of the dwellings. If these additional improvements are not required, then it is likely that there will be a physical separation between the edge of the roadway and the dwelling, due to the existing steep drop in elevation. The adjoining properties to the east and the south of the subject property would not have a widened roadway, and therefore, it would be unlikely that vehicles passing along this portion of Cliff Drive would meaningfully increase their travel speed. Further, the site development has been designed so that the northwesterly corner of the property is open and clear so that on-coming traffic could be seen more easily along this tight turn. As such, the Zoning Administrator finds that the reduction in yards will not be materially detrimental to the public welfare or injurious to the adjacent property or improvements.

Project Permit Compliance Findings

10. **The project substantially complies with the applicable regulations, findings, standards, and provisions of the specific plan.**
 - a. **Floor Area.** Per the Mount Washington/Glassell Park Specific Plan Ordinance floor area is based on a prescribed formula for properties that are greater than or equal to 5,000 square feet in size, but less than 10,000 square feet in size, by using the following equation: $0.50 - \{[(\text{Lot Area} - 5,000) \times 0.10] \div 5,000\}$. For this project, the lot size is 9,305.80 square feet, and therefore, the allowable maximum floor area ratio based on the formula is 0.43 to 1. The maximum floor area allowed is 3,696.43 square feet. Cliff Residence South measures approximately 2,380.78 square feet, including an attached parking and Cliff Residence North measures approximately 1,313.05 square feet, including a detached parking area for a total floor area of approximately 3,693.83 square feet. Therefore, the subject project would not exceed the FAR maximum allowance specified in this section of the Mount Washington/Glassell Park Specific Plan.
 - b. **Building Height and Stepback Distances.** The proposed height of Cliff Residence South will be 35 feet 9 inches, and the proposed height of Cliff Residence North will be 29 feet 2 inches, which meet the 45-foot limitation imposed by the Specific Plan. The buildings are setback in accordance with the building stepback height limitations and are in compliance with the requirements of the Specific Plan. As proposed, Cliff Residence South and Cliff Residence North meet the building stepback requirements that state that no portion of the building shall exceed 15 feet in height within the first six (6) feet of the front property line and that no portion of the building shall exceed 24 feet in height within six to 12 feet of the front property line.
 - c. **Prevailing Front Yard Setback.** The Mount Washington/Glassell Park Specific Plan's Prevailing Front Yard Setback provision does not apply because there are not at least two remaining lots for the calculation and so the proposed project's minimum front yard setback will be required as in the applicable LAMC Sections. Pursuant to LAMC Section 12.21 C.10(a) of Chapter 1, the required front yard setback is five (5) feet, and the proposed dwellings propose a zero (0) foot front yard setback through the request for relief via a Class 1 Conditional Use.
 - d. **Off-street Automobile Parking Requirements.** The property currently fronts a Substandard Hillside Limited Street that is not fully improved. The project includes a covered parking area for each proposed dwelling, which provides one (1) covered space for each dwelling and one (1) additional uncovered space for Cliff Residence South. Pursuant to LAMC Section 12.21 C.10. of Chapter 1 a third (uncovered) parking space is required if the floor area exceeds 2,400 square feet, (floor area for parking is calculated per definition of floor area pursuant to Section 12.03 of the LAMC). The project does exceed 2,400 square feet, as calculated by 12.03 of LAMC.

However, per Senate Bill 9, the project shall be required to provide one (1) covered parking space per new unit. The project has been conditioned to comply with applicable sections of the LAMC and requirements of the Department of Building and Safety.

- e. **Public Health and Safety.** Haul routes are required only when the removal of earth from on-site exceeds 1,000 cubic yards. The proposed project will export zero (0) cubic yards of soil from the subject site, and therefore, the project is compliant with Section 6.E of the Mount Washington/Glassell Park Specific Plan and the LAMC.
- f. **Landscaping and preservation, relocation, and removal of native and significant trees.** Julio Matos, consulting Arborist (#WE-9101A) indicated there are three (3) Protected Trees and three (3) Significant Trees on site. No on-site Protected Trees and one (1) Significant Tree are proposed for removal as part of the project. There is one (1) Protected Street Tree. The one (1) Protected Street Tree is proposed for removal. The project shall provide Replacement Trees per the Code for the one (1) Protected Street Tree being removed. One (1) Replacement Tree will be planted on a 1:1 ratio for the one (1) Significant Tree being removed. This Tree Report was reviewed by the Urban Forestry Division on September 16, 2025.
- g. **The architectural design elements of the front and rear building elevations vary from the adjacent buildings.** The Mount Washington/Glassell Park Specific Plan requires variation of design including façade articulation and design of differing materials, architectural details and location of windows, doors, columns, and balconies, facades that modulate with offsets or curves, insets and use of a variety of roof treatments, including roof type, shape and pitch and that such variation distinguishes it from homes on either side. The architectural plans attached to the subject file indicate that the architectural design elements will vary from the adjacent buildings based on the requirements of Section 8 for single-family design variation outlined in the Specific Plan.

The proposed designs of Cliff Residence South and Cliff Residence North are modern in style. Both residences incorporate a light-colored stucco or similar exterior finish with metal roofing. Cliff Residence South, the larger of the two proposed residences, includes an inset primary entrance, varied roof pitches, and multiple facade projections that create architectural variation. The design also incorporates balconies with glazing, which contributes to visual transparency along elevations. Cliff Residence North still modern in style maintains a more symmetrical and rectangular massing with a flatter roof. The proposed design incorporates select architectural projections and large-scale windows, particularly along the east elevation which provides modulation and greater transparency.

The property directly south at 3578 Tacoma Avenue is located on a down-sloping lot. The primary dwelling is not visible from the right-of-way, but the

garage is. The garage features a contemporary style with a traditional gabled roof, dark colored stucco finish, and black garage door and trim.

As proposed, the architectural elevations and sections are in conformance with the Design Variation standards contained in Section 8-C of the Mount Washington/Glassell Park Specific Plan.

11. **The project incorporates mitigation measures, monitoring measures when necessary, or alternatives identified in the environmental review, which would mitigate the negative environmental effects of the project, to the extent physically feasible.**

It is determined that based on the whole of the administrative record, the project is exempt from CEQA pursuant to State CEQA Guidelines Article 19, Section 15303, Class 3 for one single-family residence, or a second dwelling unit in a residential zone, and there is no substantial evidence demonstrating that an exception pursuant to CEQA Guidelines, Section 15300.2 applies.

ADDITIONAL MANDATORY FINDINGS

12. **Flood Hazard.** The National Flood Insurance Program rate maps, which are a part of the Flood Hazard Management Specific Plan adopted by the City Council by Ordinance No. 172,081, have been reviewed and it has been determined that this project is located in Zone X, areas determined to be outside the 0.2% annual chance flood plain.

APPEAL PERIOD - EFFECTIVE DATE

This grant is not a permit or license and any permits and/or licenses required by law must be obtained from the proper public agency. If any Condition of this grant is violated or not complied with, then the applicant or their successor in interest may be prosecuted for violating these Conditions the same as for any violation of the requirements contained in the Los Angeles Municipal Code (LAMC).

This determination will become effective after the end of appeal period date on the first page of this document, unless an appeal is filed with the Department of City Planning. An appeal application must be submitted and paid for before 4:30 PM (PST) on the final day to appeal the determination. Should the final day fall on a weekend or legal City holiday, the time for filing an appeal shall be extended to 4:30 PM (PST) on the next succeeding working day. Appeals should be filed early to ensure the Development Services Center (DSC) staff has adequate time to review and accept the documents, and to allow appellants time to submit payment.

An appeal may be filed utilizing the following options:

Online Application System (OAS): The OAS (<https://planning.lacity.org/oas>) allows entitlement appeals to be submitted entirely electronically by allowing an appellant to fill out and submit an appeal application online directly to City Planning's DSC, and submit fee payment by credit card or e-check.

Drop off at DSC. Appeals of this determination can be submitted in-person at the Metro or Van Nuys DSC locations, and payment can be made by credit card or check. City Planning has established drop-off areas at the DSCs with physical boxes where appellants can drop off appeal applications; alternatively, appeal applications can be filed with staff at DSC public counters. Appeal applications must be on the prescribed forms, and accompanied by the required fee and a copy of the determination letter. Appeal applications shall be received by the DSC public counter and paid for on or before the above date or the appeal will not be accepted.

Forms are available online at <http://planning.lacity.org/development-services/forms>. Public offices are located at:

Metro DSC

(213) 482-7077
201 North Figueroa Street
Los Angeles, CA 90012
planning.figcounter@lacity.org

Van Nuys DSC

(818) 374-5050
6262 Van Nuys Boulevard
Van Nuys, CA 91401
planning.mbc2@lacity.org

South Los Angeles DSC

(In person appointments available on
Tuesdays and Thursdays 8am-4pm only)
8475 S. Vermont Avenue, 1st Floor
Los Angeles, CA 90044
planning.southla@lacity.org

West Los Angeles DSC

(CURRENTLY CLOSED)
(310) 231-2901
1828 Sawtelle Boulevard
West Los Angeles, CA 90025
planning.westla@lacity.org

City Planning staff may follow up with the appellant via email and/or phone if there are any questions or missing materials in the appeal submission, to ensure that the appeal package is complete and meets the applicable LAMC provisions.

If you seek judicial review of any decision of the City pursuant to California Code of Civil Procedure Section 1094.5, the petition for writ of mandate pursuant to that section must be filed no later than the 90th day following the date on which the City's decision became final pursuant to California Code of Civil Procedure Section 1094.6. There may be other time limits which also affect your ability to seek judicial review.

Verification of condition compliance with building plans and/or building permit applications are done at the City Planning Metro or Valley DSC locations. An in-person or virtual appointment for Condition Clearance can be made through the City's [BuildLA](https://build.la) portal (appointments.lacity.org). The applicant is further advised to notify any consultant representing you of this requirement as well.



QR Code to Online
Appeal Filing



QR Code to Forms for In-
Person Appeal Filing



QR Code to BuildLA
Appointment Portal for
Condition Clearance

Inquiries regarding this matter shall be directed to Andrea Magaña Withers, Planning staff, at andrea.maganawithers@lacity.org or (213) 978-1285.


A handwritten signature in blue ink, appearing to read 'Jonathan A. Hershey', written over a horizontal line.

JONATHAN A. HERSHEY, AICP
Associate Zoning Administrator

JAH:NS:AMW:mc

cc: Councilmember Eunisses Hernandez
First District
Arroyo Seco Neighborhood Council
Adjoining Property Owners

A-SERIES DRAWINGS: CLIFF RESIDENCE SOUTH



(NAME)
 (OFF RESOURCES PROJECT)
 HALLIE BLACK - APPLICANT, OWNER (AS THE, (LL)
 (SCOPE OF WORK)
 TWO-UNIT SINGLE-FAMILY DEVELOPMENT
 (PROPOSED OCCUPANCY)
 (R#)
 (PROPOSED CONSTRUCTION)
 TYPE VB
 (APPLICABLE ZONING CODES)
 HAZARD AREA & DISORDERLY
 VERY HIGH FIRE HAZARD SEVERITY CODE
 MOUNTAIN RIDGE B-SUBSET PARKWAY SP/ORD PL
 (APPLICABLE BUILDING CODES)
 I.A.M.C. 2013
 I.A.M.C. 2023
 TITLE 24 CCR 2022

(NOTE ON 5d.9 AND RELIEF REQUEST)

OBJECTIVE ZONING, SUBDIVISION OR DESIGN REVIEW STANDARDS THAT WOULD HAVE THE EFFECT OF PHYSICALLY PRECLUDING AN URBAN LOT SPLIT, THE CONSTRUCTION OF UP TO TWO UNITS, OR PHYSICALLY PRECLUDING EITHER OF THE TWO UNITS FROM BEING NO MORE THAN 10 FEET IN FLOOR AREA, MAY NOT BE IMPOSED. ADDITIONALLY, THE DEPUTY ADVISORY AGENCY WILL NOTE WAIVERS TO ALLOW DEVIATIONS FROM LOT OR DEVELOPMENT STANDARDS IN THE URBAN LOT SPLIT DESIGNER LETTER. REGISTERED WAIVERS TO ALLOW DEVIATIONS ASSOCIATED WITH BUILDING PERMIT APPLICATIONS WITH LAGRS FOR TWO UNIT DEVELOPMENTS SHALL BE REVIEWED BY CITY PLANNING, CASE MANAGEMENT AS PART OF THE PLAN CHECK REVIEW PROCESS.

THIS PROJECT DOES NOT IMMEDIATELY QUALIFY FOR RELIEF FROM THE OBJECTIVE DESIGN STANDARDS SB-9. HOWEVER, GIVEN THE SITE'S CONSTRAINTS, FAILURE TO OBTAIN THIS RELIEF WOULD PHYSICALLY PRECLUDE FUTURE DEVELOPMENT OF AN ADDITIONAL UNIT OF AT LEAST ONEHOF. THIS, TO ALIGN WITH SB-9'S PURPOSE TO INCREASE HOUSING DENSITY, RELIEF FROM THIS REQUIREMENT IS NECESSARY. SEE ACTIONS REQUEST NARRATIVE ON WHY THIS RELIEF REQUEST IS CRUCIAL TO PRESERVE THE FEASIBILITY OF A TWO-UNIT/URBAN LOT SPLIT DEVELOPMENT.

THIS PROPOSAL INCLUDES CLIFF RESIDENCE NORTH AND PROPOSED SUBDIVISION REFERRED TO HEREIN AS "UNDER FUTURE PHASED SE-8", IN THE CITY ADMINISTRATIVE REVIEW APPLICATION DUE TO THE PHYSICAL PRECLUSION OF DEVELOPMENT STANDARDS.

TWO-UNIT DEVELOPMENT

THE PROPOSAL REQUESTS A CLASS 1 CONDITIONAL USE PERMIT FROM HILLER FROM THE FOLLOWING BASELINE HILLSIDE GRADIENT ZONING REQUIREMENTS:

1. AUTHORIZED CODE SECTION LANE 8 12.31 X 20.00, CODE SECTION FROM WHICH HILLER REQUESTED LANE 8 12.31 C 10.00. ACTION REQUESTED: MINIMUM 8 FT FRONT YARD SETBACK REQUIREMENT FROM SUBSTANDARD HILLSIDE LIMITED STREET TO 8 FT ALONG TWO PORTIONS TOTALING 61% OF THE TOTAL 219 FT. MIN FRONTAGE.

2. AUTHORIZING CODE SECTION LANE & 12.36 ALPHABETIC CODE SECTION FROM WHICH RELIEF IS REQUESTED LANE & 12.21 C CODE, ACTION REQUESTED OUTSIDE THE PORT STREET IMPROVEMENT TO OUTSIDE HILLSIDE AREA BOUNDARY REQUIREMENT.

ADDITIONALLY, THE FOLLOWING MAY BE SUBJECT TO A CUP:

3. AUTHORIZING CODE SECTION LAMC 8.22.2; CODE SECTION FROM WHICH RELIEF IS REQUESTED: LAMC 12.21 C.288; ACTION REQUESTED: WAIVE LEFT CLEAR PATH TO NORTH LOT DUE TO EXTENDING THE ADJUTING RETAINING WALL TO THE SIDE LOT LINE TO PROVIDE AN 8-FOOT-WIDE PASSAGEWAY FOR LEGS FOR CLIFF RESIDENCE NORTH IN LIEU OF 10-FOOT PASSAGEWAY AS REQUIRED.

SEE ACTION REQUEST NARRATIVE FOR ALL ABOVE RELIEF REQUESTS.

SEE ACTION REQUEST NARRATIVE FOR ALL ABOVE RELIEF REQUESTS

TWO-UNIT DEVELOPMENT

SEE SWS-004.0 AND -005.0 W/NOT SPECIFIC PLAN ZONING CALCULATION FOR FLOOR AREAS

(MAXIMUM BUILDING HEIGHT)
2 STORES
30FT-300

ELEVATION WITHIN STEPBACK ENVELOPES PER HYDRO SPECIFIC PLAN]
BETWEEN 0' AND 6", 14'-6" (SEE NORTH UNIT STEPBACK DIAGRAM)
BETWEEN 6' AND 12'-25", 8" (SEE SOUTH UNIT STEPBACK DIAGRAM)

SEE SYS-804.0 GENERAL NOTES FOR STEPS/BACK DIMENSION ENVELOPE DIAGRAM

B GENERAL		
0.000	NUMBER, SERIES	
0.001	EXPONENTIAL	NA 0.076
0.002	COSINE, HALF	NA 0.076
0.003	COSINE, FULL	NA 0.076
0.004	SINE, HALF	NA 0.076
0.005	SINE, FULL	NA 0.076
0.006	EXPONENTIAL	NA 0.076
0.007	EXPONENTIAL, 100-DEG	7.0E-07 0.076
0.008	SINUS, COS, PHASE	1.0E-12 0.076
0.009	TAN, CO-TAN, TAN-1, PHAS	1.0E-12 0.076
0.010	LOG, LOG10, LOG10-10	1.0E-12 0.076
0.011	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.012	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.013	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.014	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.015	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.016	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.017	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.018	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.019	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.020	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.021	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.022	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.023	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.024	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.025	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.026	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.027	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.028	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.029	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.030	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.031	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.032	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.033	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.034	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.035	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.036	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.037	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.038	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.039	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.040	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.041	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.042	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.043	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.044	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.045	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.046	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.047	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.048	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.049	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.050	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.051	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.052	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.053	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.054	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.055	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.056	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.057	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.058	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.059	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.060	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.061	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.062	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.063	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.064	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.065	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.066	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.067	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.068	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.069	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.070	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.071	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.072	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.073	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.074	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.075	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.076	EXPONENTIAL, 100-DEG	1.0E-12 0.076
0.077		

ALL COMMENTS ON GREEN MUST BE
RECEIVED BY 05/01/97. APPLICATIONS
ITEMS IN RED ARE STILL PENDING
ITEMS IN BLUE ARE NOT REQUIRED TO
ACHIEVE 100% FOR FIRM. SOME OFF. HELD
REQUIRED FOR PERMIT ISSUANCE
ITEMS IN MAGENTA ARE CANCELLED.

SEE COMMENT ON RETAINING WALL

PLEASE PROVIDE WRITTEN RESPONSE TO COMMENT
ON PLANS AND THE CORRECTION SHEETS

PROVIDE A COPY ON PLAN SIGNED SRB OWNER
DECLARATION RELATED TO TENANT OCCUPANCY
FORM CAN BE OBTAINED FROM LADBS WEBSITE

OBTAIN CLEARANCE FROM ALL DEPARTMENTS LISTED ON THE CLEARANCE SUMMARY WORKSHEET PRIOR TO REQUESTING CLEARANCE AND FINAL APPROVAL FROM ZONING DEPARTMENT

APPLICANT TO REVIEW SECTION 8.6 OF THE 889 CHECKLIST TO DETERMINE WHETHER HABITAT FOR PROTECTED SPECIES EXISTS ON THE PARCEL IN ORDER AS REQUIRED PER SECTION 66913.4(A)(1)(J).

IF THE ELIGIBILITY CRITERIA CHECKLIST STATES "NO" SUBMIT THE OWNER'S DECLARATION OF NO HABITAT (CP-36580). IF IT STATES "BIO REVIEW NEEDED", SUBMIT THE BIOLOGIST'S STATEMENT OF HABITAT (CP-36192).

LABOR APPROVAL STAMP:




PROJECT NUMBER: 00039LI
PHASE: ZONING/PERMITTING REVIEW
DATE: 07/02/2025
SCALE: NA

COVER SHEET
G-000.0


TWO-UNIT DEVELOPMENT ZONING SETBACK DIAGRAMS

EXISTING SITE ZONING SETBACKS




CONDITIONS REGARDLESS OF SB9
DEVELOPMENT

TWO-UNIT DEVELOPMENT PRE-SUBDIVISION ZONING SETBACKS



EXISTING FILING FOR TUD WITH LADBS


CU1 VARINACE REQUEST PRE-SUBDIVISION ZONING SETBACKS



CURRENT FILING OF CU1 FRONT YARD
SET BACK DIMINISHMENT AND WAIVING
OF 3FT DEDICATION

TWO-UNIT DEVELOPMENT ZONING SETBACK DIAGRAM W/ CU1 FRONT YARD SETBACK DIMINISHMENT

SINGLE FAMILY DEVELOPMENTS ZONING SETBACKS



CLIFF RES. S
X2 LEVELS
1,200 SQ.FT FOOTPRINT
CLIFF RES. N
X2 LEVELS
650 SQ.FT FOOTPRINT

NOTE

3FT DEDICATION TO BE WAIVED DURING CU1
PROCESS TO CONVERT 0FT FRONT YARD
SETBACK TO 3FT FRONT YARD SETBACK
WHERE APPLICABLE

PROJECT
**CLIFF
RESIDENCE
PROJECT**
FUNDING
PROJECT ADDRESS
APN5454013026
1236 N CLIFF DR
LOS ANGELES, CA 90065

OWNER:
AS THE CROW, LLC
1431 4TH STREET
SANTA MONICA, CA 90405
TEL: +1 (310) 443-8518
HALLIE@BLACKHOLE.COM

DESIGNER:
HALLIE BLACK
2127 HILLSIDE DRIVE
TORRANCE, CA 90503
TEL: +1 (310) 443-8518
HALLIE@BLACKHOLE.COM

EXECUTIVE ARCHITECTS:
**ARCHITECTURE
STUDIO SEO PLLC**
309 N 2ND ST, 102
NEW YORK, NY 10012
TEL: +1 (212) 775-3300
OO@STUDIOSEO.COM

CIVIL ENGINEER:
**WEST COAST TECHNICAL
CONSULTANTS, INC**
1001 EAST LOS ANGELES AVE, C105
SUN VALLEY, CA 91355
TEL: +1 (818) 744-1661
DAVID@WCTC.COM

STRUCTURE ENGINEER:
**POLON & LEWIS
STRUCT ENGINEERING, INC**
5301 BETHUNE ST, STE 100
LOS ANGELES, CA 90046
TEL: +1 (310) 796-3410
OFFICE@POLON-LEWIS.COM



ISSUES / REVISIONS	DATE	SYMBOL	DESCRIPTION
2015-05-01			SUBMISSION
2015-05-21			REVISION 7
2015-06-10			REVISION 8
2015-05-01			PLANS
2015-05-20			PLANS REVISION 1

LAWS APPROVAL STAMP:




EXHIBIT "A"
Page No. 2 of 17
Case No. ZA-2025-2856-CU1-SMPC-HCA



PROJECT NUMBER: 0000001
PROJECT: ZONING/PERMITTING REVIEW
DATE: 07/27/2025
SCALE: NA

SITE ANALYSIS
G-005.0

TWO-UNIT DEVELOPMENT STEPBACK DIAGRAMS



MAP KEY



TWO-UNIT DEVELOPMENT TREE TABLES

TREE	EXISTING	REPLANTATION	REMOVED	REPLANT	TOTAL	NOTE
PROTECTED, ON PROPERTY	2	4 IN 1 IN.	0	0	2	ALL TO REMAIN
SHARP LEAF, 1/2" THICK, ON PROPERTY	3	1 IN 1	1	1	3	ONE TO BE REMOVED DURING POOR HEALTH. ALL OTHERS TO REMAIN
PROTECTED, OFF PROPERTY	2	4 IN 1 IN.	1	1	2	ONE TO BE REMOVED DURING STREET WORKS. ALL OTHERS TO REMAIN

TREE LEGEND	HEIGHT	SIZE	NOTE
SAFIA (CROTONA) (SILVER)	1	24" DIA. @ 10 FT. TALL	TO BE PLANTED ON PROPERTY, FOR 11 REPLANTING REQUIREMENT
METROPOLES ARBUTUS (TIDY)	4	15" DIA. @ 10 FT. TALL	TO BE PLANTED ON PROPERTY, FOR 4.5 REPLANTING REQUIREMENT
ABOVE AMERICAN (SILVER, WAXED) (WAXED)	7	15" DIA. @ 10 FT. TALL	TO BE PLANTED ON PROPERTY
ABOVE SYCAMORE (SILVER, WAXED) (WAXED)	3	15" DIA. @ 10 FT. TALL	TO BE PLANTED ON PROPERTY

GRADING TABLE

GRADING	TOTAL GRADING CUBIC YD	ALL IN PLACE** CUT/FILL CUBIC YD	PROPOSED CUT CUBIC YD	PROPOSED FILL CUBIC YD	EXEMPTION
AREA	344.548	104.120	64.350	64.350	
EXEMPTED SHAPE			30.440	44.050	EXEMPT (INTERNAL GRADING)
SHOULDER LVL. GRADING LEVEL/BASEMENT			17.130	58.220	EXEMPT (FOUNDATION)
SHOULDER LVL. BASEMENT			16.380	28.980	EXEMPT (FOUNDATION)
PAVING			14.111	7.718	
CUT (EXEMPT) (SILVER)			14.111	7.718	
FILL (EXEMPT) (SILVER)			14.111	7.718	
TOTAL	385.409	111.250	122.342	163.068	
BALANCE GRADING			64.350	64.350	
SHOULDER		375.059			NON-EXEMPT
EXEMPT		758.303			NON-EXEMPT

* BASED ON GRADING AND DRAINAGE PLAN DATED 07-10-2025 PREPARED BY WCTE INC. YARDAGE INCLUDES THICKNESS OF WALLS AND FOOTINGS AS SHOWN IN SECTIONS CONTOUR METHOD
** 50% CUT/VOID PLUS THE REMAINING VALUE EQUAL TO 5% OF THE TOTAL LOT SIZE IN CUBIC YD

RETAINING WALL SCHEDULE

RETAINING WALL SCHEDULE	TOTAL	MAXIMUM HEIGHT	NOTE
EXISTING	1	5 FT	TO BE BACKFILLED OVER AND DEEMED NO LONGER IN USE PER LADS GRADING
ABUTTING ATTACHED	1	10 FT	ALONG NORTH LOT LINE TO SUPPORT PUBLIC WAY
PROPOSED	1	10 FT	ALONG THE EAST LOT LINE FOR SLOPE TYPING
TOTAL PER BUILDING LINE	3		

PER LINE ITEM 12.1.1 - RETAINING WALLS IN INCLUDE AREAS RETAINING WALLS IN BUILDING AREAS, A "RETAINING WALL" SHALL BE DEEMED AS A PERMANENT CONTIGUOUS STRUCTURE, AS VIEWED FROM THE TOP, INTENDED TO SUPPORT EARTH, WHICH IS NOT ATTACHED TO A BUILDING

PROJECT:
**CLIFF
RESIDENCE
PROJECT**
PROJECT ADDRESS:
**APN5454013026
1236 N CLIFF DR
LOS ANGELES, CA 90065**
OWNER:
AS THE CROW, LLC
2811 8TH STREET
SANTA MONICA, CA 90405
TEL: +1 (310) 443-8518
HALLIEBLACK@GMAIL.COM

DESIGNER:
HALLIE BLACK
2107 HILLSIDE DRIVE
TOPANGA, CA 90290
TEL: +1 (310) 443-8518
HALLIEBLACK@GMAIL.COM

EXECUTIVE ARCHITECT:
**ARCHITECTURE
STUDIO SEO PLLC**
300 W 82ND ST, 100
NEW YORK, NY 10024
TEL: +1 (212) 795-1300
STUDIOSEO@GMAIL.COM

CIVIL ENGINEER:
**WEST COAST TECHNICAL
CONSULTANTS, INC**
1011 EAST LOS ANGELES AVE, CIVIL
SAN ANGELES, CA 76901
TEL: +1 (817) 266-5554
DAVID@WCTC.COM

STRUCTURE ENGINEER:
**POLON & LEWIS
STRUCTURAL ENGINEERING, INC**
4300 WESTBROOK ST, STE. 200
LOS ANGELES, CA 90066
TEL: +1 (310) 494-5450
OFFICE@POLON-LEWIS.COM




ISSUES / REVISIONS:		
DATE	SYMBOL	DESCRIPTION
7/25/05-09		SUBMISSION
7/25/05-31		REVISION 1
7/25/05-10		REVISION 2
10/5/05-09		FILING
7/25/05-30		FILING REVISION 1
		</

1236 N CLIFF DRIVE

NOTE
AS NO PORTION OF THE NEARBY ROADWAY ENTERS INTO THE SITE, THE PROPOSAL REQUESTS A WAIVER OF THE 3% DEDICATION REQUIREMENT IN LIEU OF A 3% DEDICATION FRONT YARD SETBACK AND INSTEAD FOR A 3% DEDICATION FRONT YARD SETBACK WHERE LOCATED.

SEE ACTION REQUEST NARRATIVE AND FIGURE 1000 FOR STREET DEDICATION AND IMPROVEMENTS.



ITEM	DESCRIPTION	QUANTITY	UNIT	PRICE	TOTAL
1	PROPOSED RETAINING WALL	1	LINEAL FOOT	100.00	100.00
2	PROPOSED RETAINING WALL	1	LINEAL FOOT	100.00	100.00
3	PROPOSED RETAINING WALL	1	LINEAL FOOT	100.00	100.00
4	PROPOSED RETAINING WALL	1	LINEAL FOOT	100.00	100.00
5	PROPOSED RETAINING WALL	1	LINEAL FOOT	100.00	100.00
6	PROPOSED RETAINING WALL	1	LINEAL FOOT	100.00	100.00
7	PROPOSED RETAINING WALL	1	LINEAL FOOT	100.00	100.00
8	PROPOSED RETAINING WALL	1	LINEAL FOOT	100.00	100.00
9	PROPOSED RETAINING WALL	1	LINEAL FOOT	100.00	100.00
10	PROPOSED RETAINING WALL	1	LINEAL FOOT	100.00	100.00

Added retaining wall schedule



EXHIBIT "A"
Page No. 5 of 17
Case No. ZA-2025-285-CUI-SPPC-HCA

PROPOSED LANDSCAPE PLAN
SCALE - FULL (1/4"=1'-0") 1/4" = 1'-0"
CL-4-SITE PLAN

CLIFF RESIDENCE PROJECT

PROJECT ADDRESS:
APN5454013026
1236 N CLIFF DR
LOS ANGELES, CA 90065

OWNER:
AS THE CROW, LLC
3841 8TH STREET
SANTA MONICA, CA 90405
TEL: +1 (310) 441-8818
HALLIE@BLACKBLK.COM

DESIGNER:
HALLIE BLACK
2127 HILLGATE DRIVE
TOPANMA, CA 90290
TEL: +1 (310) 441-8818
HALLIE@BLACKBLK.COM

EXECUTIVE ARCHITECT:
ARCHITECTURE STUDIO SEO PLLC
308 W 82ND ST, 10
NEW YORK, NY 10024
TEL: +1 (212) 791-3200
CONTACT@STUDIOSEO.COM

CIVIL ENGINEER:
WEST COAST TECHNICAL CONSULTANTS, INC
101 EAST LOS ANGELES AVE, C105
SUN VALLEY, CA 91355
TEL: +1 (818) 216-8284
DAN@WCTCINC.COM

STRUCTURE ENGINEER:
POLO & LEWIS STRUCT ENGINEERING, INC
5700 BEETHOVEN ST, STE 200
LOS ANGELES, CA 90044
TEL: +1 (213) 598-5551
OFFICE@POLO-LEWIS.COM




DATE	SYMBOL	DESCRIPTION
2024-05-09	1	PRELIMINARY
2025-03-21	2	REVISION 7
2025-04-10	3	REVISION 8
2025-05-09	4	REVISION 9
2025-05-30	5	REVISION 10

PROJECT NUMBER: 100301
PHASE: ZONING/PERMITTING REVIEW
DATE: 01/05/2025
SCALE: 1/8" = 1'-0"

PROPOSED LANDSCAPE PLAN
G-022.0

CLIFF RESIDENCE SOUTH



A1 - WEST ELEVATION WITH FRONT ENTRY LOOKING EAST FROM CLIFF DR



A2 - SOUTH AND EAST ELEVATION LOOKING NORTH WEST FROM DOWNSLOPE



A3 - NORTH ELEVATION WITH SIDE ENTRANCE LOOKING SOUTH FROM DRIVEWAY ENTRY

EXHIBIT "A"
Page No. 6 of 17
Case No. ZA-2025-2856-CU1-SPPC-HCA

PROJECT
CLIFF
RESIDENCE
PROJECT
NEW CONSTRUCTION

PROJECT ADDRESS
APN5454013026
1236 N CLIFF DR
LOS ANGELES, CA 90065

OWNER
AS THE CROW, LLC
3834 6TH STREET
SANTA MONICA, CA 90405
TEL: +1 (310) 444-2516
HALLIEBLACK@GMAIL.COM

DESIGNER
HALLIE BLACK
1107 MILLER DRIVE
TORRANCE, CA 90501
TEL: +1 (310) 644-8518
HALLIEBLACK@GMAIL.COM

EXECUTIVE ARCHITECT
ARCHITECTURE
STUDIO SEO PLLC
380 W 62ND ST, 10
NEW YORK, NY 10019
TEL: +1 (212) 749-1100
STUDIOSEO@GMAIL.COM

CIVIL ENGINEER
WEST COAST TECHNICAL
CONSULTANTS, INC
1001 EAST LOS ANGELES AVE, C10
SUN VALLEY, CA 91351
TEL: +1 (818) 318-8504
DAN@WCTC.COM

STRUCTURE ENGINEER
POLON & LEWIS
STRUCT ENGINEERING, INC
5301 BEETHOVEN ST, STE 200
LOS ANGELES, CA 90033
TEL: +1 (310) 798-5801
OFFICE@POLON-LEWIS.COM




ISSUES / REVISIONS		
DATE	DESCRIPTION	REVISION
2024-05-09	SUBMISSION	
2025-03-21	REVISION 1	
2025-04-15	REVISION 2	
2025-05-09	FILED	
2025-05-09	FILED	REVISION 1

LANDS APPROVAL STAMP

PROJECT NUMBER: 000101
PHASE: ZONING/PERMITTING REVIEW
DATE: 6/10/2025
SCALE: N/A

RENDERING
A-001.0



REVISIONS

1. GLASS A ROOF COVERING IS REQUIRED FOR ALL BUILDINGS. WOOD, SHAKES AND SHINGLES ARE NOT PERMITTED. (7701.4, 1051)
2. VALLEY FLASHINGS SHALL BE NOT LESS THAN 24 INCHES (610 MM) BROAD. GALVANIZED SHEET GASKET CONSTRUCTION-RESISTANT METAL INSTALLED OVER A MINIMUM 24 INCH (610 MM) BROAD OPENING OR ITS EQUIVALENT. VENTS SHALL NOT BE INSTALLED IN EAVES AND CORNICES (7704.1, 7804.2, 7804.3, 7804.4)
3. ROOF GUTTERS SHALL BE PROVIDED WITH THE MEANS TO PREVENT THE ACCUMULATION OF LEAVES AND DEBRIS IN THE GUTTER (7705.4)
4. BRICK (TILE) EXTERIOR WALLS SHALL RESIST THE INTRUSION OF FLAME AND PASS INTO THE ATTIC AREA OF THE STRUCTURE. OR SHALL BE PROTECTED BY CORROSION-RESISTANT NONCOMBUSTIBLE WIRE MESH WITH 1/4 INCH (6.35 MM) SPACING OR ITS EQUIVALENT. VENTS SHALL NOT BE INSTALLED IN EAVES AND CORNICES (7704.1, 7804.2, 7804.3, 7804.4)
5. EAVES AND SOFFITS SHALL MEET THE REQUIREMENTS OF SPH 12-1A-2 OR SHALL BE PROTECTED BY CORROSION-RESISTANT MATERIALS OR NONCOMBUSTIBLE CONSTRUCTION ON THE EXPOSED UNDERSIDE (7707.1)
6. EXTERIOR WALLS SHALL BE APPROVED NONCOMBUSTIBLE OR CORROSION-RESISTANT MATERIAL, HEAVY TIMBER, OR LOW WALL CONSTRUCTION OR SHALL PROVIDE PROTECTION FROM THE INTRUSION OF FLAMES AND DEBRIS IN ACCORDANCE WITH STANDARD SPH 12-1A-1 (7707.1)
7. EXTERIOR WALL COVERINGS SHALL EXTEND FROM THE TOP OF FOUNDATION TO THE ROOF, AND TERMINATE AT EACH 50-8 INCH (1275 MM) MINIMUM SOLID WOOD BLOCCING BETWEEN RAFTERS AT ALL ROOF OVERHANGS. OR IN THE CASE OF ENCLOSED EAVES, TERMINATE AT THE ENCLOSURE (7704.1, 7804.2)
8. EXTERIOR WINDOWS, WINDOW WALLS, GLAZED DOORS, AND GLAZED OPENINGS WITHIN EXTERIOR DOORS SHALL BE REGULATING-GLASS UNITS WITH A MINIMUM OF ONE TYPED FRAME, OR GLASS BLOCK UNITS, OR HAVE A FIRE-RESISTANCE RATING OF NOT LESS THAN 20 MINUTES. UNITS TESTED ACCORDING TO NFPA 253, OR CONFORM TO THE PERFORMANCE REQUIREMENTS OF SPH 12-1A-2 (7704.1, 7804.2)
9. EXTERIOR DOOR ASSEMBLIES SHALL CONFORM TO THE PERFORMANCE REQUIREMENTS OF STANDARD SPH 12-1A-1 OR SHALL BE APPROVED NONCOMBUSTIBLE CONSTRUCTION OR SOLID CORE WOOD HAVING STILES AND RAILS NOT LESS THAN 1 3/8 INCHES THICK WITH INTERIOR FILL PANEL THICKNESS NO LESS THAN 1 1/4 INCHES THICK. OR SHALL HAVE A FIRE-RESISTANCE RATING OF NOT LESS THAN 20 MINUTES WHEN TESTED ACCORDING TO NFPA 253. EXCEPT NONCOMBUSTIBLE OR EXTERIOR FIRE-RESISTANT TREATED WOOD VEHICLE ACCESS DOORS (7704.1, 7804.2)
10. DECKING, SURFACES, STAIR TREADS, RISERS, AND LANDINGS OF DECKS, PORCHES, AND BALCONIES WHERE ANY PORTION OF SUCH SURFACE IS WITHIN 10 FEET (3048 MM) OF THE PRIMARY STRUCTURE SHALL BE CONSTRUCTED OF HEAVY TIMBER, NONCOMBUSTIBLE OR OTHER APPROVED MATERIALS PER SEC 7004.3
11. THE UNDERSIDE OF CANTILEVERED AND OVERHANGING APPENDAGES AND FLOOR PROJECTIONS SHALL MAINTAIN THE EXISTING, RESISTANT INTEGRITY OF EXTERIOR WALLS. OR THE PROJECTION SHALL BE ENCLOSED TO THE GRADE (7707.1)
12. BUILDINGS SHALL HAVE ALL UNDERFLOOR AREAS COMPLETELY ENCLOSED TO THE GRADE WITH CONSTRUCTION AS REQUIRED FOR EXTERIOR WALLS (7704.1, 7804.2)
13. ALL UTILITIES, PIPES, FURNACES, WATER HEATERS OR OTHER MECHANICAL DEVICES LOCATED IN AN EXPOSED UNDER-FLOOR AREA OF A RESIDENTIAL BUILDING SHALL BE ENCLOSED WITH MATERIALS AS REQUIRED FOR 1-HOUR FIRE-RESISTIVE CONSTRUCTION (7707.1)
14. THE SPACE BETWEEN THE ROOF COVERING AND ROOF DECKING SHALL BE CONSTRUCTED TO PREVENT THE INTRUSION OF FLAMES AND DEBRIS AND BE FIRE STOPPED PER 7004.7

PROJECT

CLIFF RESIDENCE PROJECT
 PROJECT ADDRESS:
APN5454013026
1236 N CLIFF DR
LOS ANGELES, CA 90065

OWNER:
AS THE CROW, LLC
 7836 4TH STREET
 SANTA MONICA, CA 90405
 TEL: +1 (310) 441-8008
 HALLIE@BLACKPINE.COM

DESIGNER:
HALLIE BLACK
 2127 HILLTOP DRIVE
 TOLAND, CA 95058
 TEL: +1 (916) 344-8008
 HALLIE@BLACKPINE.COM

EXECUTIVE ARCHITECT:
ARCHITECTURE STUDIO SEO PLLC
 300 W 2ND ST, 10
 NEW YORK, NY 10014
 TEL: +1 (212) 779-2000
 CDO@STUDIOSEO.COM

CIVIL ENGINEER:
WEST COAST TECHNICAL CONSULTANTS, INC.
 101 EAST LOS ANGELES AVE, CTS
 SUN VALLEY, CA 91350
 TEL: +1 (818) 774-7000
 CANTON@WCTC.COM

STRUCTURE ENGINEER:
POLON & LEWIS STRUCT ENGINEERING, INC.
 5301 BELLEVUE ST, STE 200
 LOS ANGELES, CA 90044
 TEL: +1 (310) 998-5811
 OFFICE@POLON-LEWIS.COM



DATE	SYMBOL	DESCRIPTION
2024-05-09		SUBMISSION
2025-03-27		REVISION 1
2025-04-10		REVISION 2
2025-05-09		FILED
2025-05-30		FILED REVISION 1


CITY OF LOS ANGELES, DEPARTMENT OF BUILDING AND SAFETY
 PRELIMINARY ZONING ASSESSMENT COMPLETE
 BY: RONALD ORSMEAD
 DATE: 07/10/2025
 APPLICATION #: 24010 - 00001 - 00002

PROJECT NUMBER: 000333
 PHASE: ZONING/PLANNING REVIEW
 DATE: 07/07/2025
 SCALE: 1/4" = 1'-0"

FLOOR PLAN FIRST FLOOR
A-101.0

EXHIBIT "A"
 Page No. 7 of 17
 Case No. 24-2025-2955-CUI-SPPC-HCA

FLOOR PLAN - FIRST FLOOR
 SCALE - FULL ON 22x34 1/2" x 7'-0"
 CL-1, 1701



- (VPMH2Z NOTES)**
1. CLASSES A ROOF COVERING IS REQUIRED FOR ALL BUILDINGS. WOOD, SHAKES AND SHINGLES ARE NOT PERMITTED. (202A, 1551)
 2. VALLEY PLUMBING SHALL BE NOT LESS THAN 0.019-INCH DIA PPH OR 1/8 GALVANIZED SHEET GAGE CORROSION-RESISTANT METAL INSTALLED OVER A MINIMUM 1/8-INCH-THICK INSULATION UNDERLAYER. COVERING OF THE LATER OF 1/2" TO 1/4" WITH CAP SHEET RUNNING THE FULL LENGTH OF THE VALLEY (197A.3)
 3. ROOF GUTTERS SHALL BE PROVIDED WITH THE MEANS TO PREVENT THE ACCUMULATION OF LEAVES AND DEBRIS IN THE GUTTER (197A.1)
 4. (ROOF) ATTIC EXTERIOR WALL VENTS SHALL RESIST THE INTRUSION OF FLAME AND EMBERS INTO THE ATTIC AREA OF THE STRUCTURE OR SHALL BE PROTECTED BY CORROSION-RESISTANT, NONCOMBUSTIBLE WIRE MESH WITH 1/8-INCH DIA HOLES OR EQUIVALENT. VENTS SHALL NOT BE INSTALLED IN EAVES AND CORNERS (197A.1, 197A.1, 197A.1, 197A.1)
 5. EAVES AND GUTTERS SHALL MEET THE REQUIREMENTS OF SPH 12-7A-3 OR SHALL BE PROTECTED BY NONCOMBUSTIBLE MATERIALS OR NONCOMBUSTIBLE CONSTRUCTION ON THE EXPOSED UNDERSIDE (197A.1)
 6. EXTERIOR WALLS SHALL BE APPROVED NONCOMBUSTIBLE OR NONTOXIC RESISTANT MATERIAL, HEAVY TIMBER, OR LOG WALL CONSTRUCTION OR SHALL PROVIDE PROTECTION FROM THE INTRUSION OF FLAMES AND EMBERS IN ACCORDANCE WITH STANDARD SPH 12-7A-1 (197A.1)
 7. EXTERIOR WALL COVERINGS SHALL EXTEND FROM THE TOP OF FOUNDATION TO THE ROOF AND TERMINATE AT 2-INCH DOOR PPH. JOINTS IN WOOD BLOCKING BETWEEN RAFTERS AT ALL ROOF OVERHANGS, OR IN THE CASE OF ENCLOSED EAVES, TERMINATE AT THE ENCLOSURE (197A.1, 197A.1)
 8. EXTERIOR WOODS, WINDOW WALLS, GLAZE COORS, AND GLAZED OPENINGS WITHIN EXTERIOR COORS SHALL BE INDICATING GLAZE UNITS WITH A MINIMUM OF ONE TEMPERED PANE, OR GLASS BLOCK UNITS, OR HAVE A FIRE-RESISTANCE RATING OF NOT LESS THAN 20 MINUTES, WHEN TESTED ACCORDING TO NFPA 251, OR CONFORM TO THE PERFORMANCE REQUIREMENTS OF SPH 12-7A-2 (197A.1)
 9. EXTERIOR DOOR ASSEMBLIES SHALL CONFORM TO THE PERFORMANCE REQUIREMENTS OF STANDARD SPH 12-7A-1 OR SHALL BE APPROVED NONCOMBUSTIBLE CONSTRUCTION, OR SOLID CORE WOOD HAVING STILES AND RALES NOT LESS THAN 1 3/8 INCHES THICK WITH INTERIOR PLY PANEL THICKNESS NOT LESS THAN 1 1/4 INCHES THICK, OR SHALL HAVE A FIRE-RESISTANCE RATING OF NOT LESS THAN 20 MINUTES WHEN TESTED ACCORDING TO NFPA 251. EXCEPTION: NONCOMBUSTIBLE OR EXTERIOR PRELAMBANT TREATED WOOD VEHICLE ACCESS DOORS (197A.1)
 10. DECORATIVE SURFACES, STAIR TREADS, RISERS, AND LANDINGS OF DECKS, PORCHES, AND BALCONIES WHERE ANY PORTION OF SOLID SURFACE IS WITHIN 6 FEET (1944 PPH) OF THE PRIMARY STRUCTURE SHALL BE CONSTRUCTED OF HEAVY TIMBER, NON COMBUSTIBLE OR OTHER APPROVED MATERIALS PER SEC. 197A.3
 11. THE UNDERSIDE OF CANTILEVERED AND OVERHANGING APPENDAGES AND ROOF PROJECTIONS SHALL MAINTAIN THE NONTOXIC-RESISTANT INTEGRITY OF EXTERIOR WALLS, OR THE PROJECTION SHALL BE ENCLOSED TO THE GRADE (197A.1)
 12. BUILDINGS SHALL HAVE ALL UNDERFLOOR AREAS COMPLETELY ENCLOSED TO THE GRADE WITH CONSTRUCTION AS REQUIRED FOR EXTERIOR WALLS (197A.1, 197A.1)
 13. ALL UTILITIES, PIPES, PURNACES, WATER HEATERS OR OTHER MECHANICAL DEVICES LOCATED IN AN EXPOSED UNDERFLOOR AREA OF A RESIDENTIAL BUILDING SHALL BE ENCLOSED WITH MATERIALS AS REQUIRED FOR UNDER FLOOR-RESISTANT CONSTRUCTION (197A.1)
 14. THE SPACE BETWEEN THE ROOF COVERINGS AND ROOF DECKS SHALL BE CONSTRUCTED TO PREVENT THE INTRUSION OF FLAMES AND EMBERS AND BE FIRE STOPPED PER 705A.2

PROJECT:
CLIFF RESIDENCE PROJECT

PROJECT ADDRESS:
APN5454013026
1236 N CLIFF DR
LOS ANGELES, CA 90065

OWNER:
AS THE CROW, LLC
 304 N 4TH STREET
 SANTA ANITA, CA 90405
 TEL: +1 (619) 444-8518
 MAIL: AS@THECROW.COM

DESIGNER:
HALLIE BLACK
 1127 HILLSIDE DRIVE
 TORRANCE, CA 90503
 TEL: +1 (415) 444-8518
 MAIL: HBLACK@GMAIL.COM

EXECUTIVE ARCHITECTS:
ARCHITECTURE
STUDIO SEO PLLC
 308 W 8TH ST, 100
 NEW YORK, NY 10013
 TEL: +1 (212) 795-3300
 CDO@STUDIOSEO.COM

CIVIL ENGINEER:
WEST COAST TECHNICAL
CONSULTANTS, INC
 101 EAST LOS ANGELES AVE, CFS
 SPM VALLEY, CA 90665
 TEL: +1 (818) 294-5555
 DAY@WCTCINC.COM

STRUCTURE ENGINEER:
POLON & LEWIS
STRUCT ENGINEERING, INC
 5341 BEDFORD ST, STE 208
 LOS ANGELES, CA 90066
 TEL: +1 (213) 994-5644
 OFFICE@POLON-LEWIS.COM



ISSUES / REVISIONS:


DATE	ISSUE	DESCRIPTION
2024-08-01	SUBMISSION	
2025-02-21	REVISION 7	
2025-08-01	REVISION 8	
2025-09-01	FILED	
2025-05-30	FILED	REVISION 1

LADES APPROVAL STAMP:

EXHIBIT "A"
 Page No. 8 of 17
 Case No. 24-2025-2856-CUI-SPHC-HCA

A1 FLOOR PLAN - SECOND FLOOR
 SCALE: FULL DIMENSIONS 1/4" = 1'-0"
 C.L.A.-P902

FLOOR PLAN SECOND FLOOR
A-102.0



- [VENDOR NOTES]
1. CLASS A ROOF COVERING IS REQUIRED FOR ALL BUILDINGS. WOOD SHAKES AND SHINGLES ARE NOT PERMITTED. (7207A, 7505I)
 2. VALLEY FLASHINGS SHALL BE NOT LESS THAN 0.019-INCH 1043 FINI HD. 18 GALVANIZED SHEET GAGE CORRUGATED-RESISTANT METAL INSTALLED OVER A MINIMUM 1/4-INCH-WIDE FISHPLANK UNDERLAMENT CONSISTING OF ONE LAYER OF 1/2 ASPH CAP SHEET RUNNING THE FULL LENGTH OF THE VALLEY (7505A.3)
 3. ROOF GUTTERS SHALL BE PROVIDED WITH THE MEANS TO PREVENT THE ACCUMULATION OF LEAVES AND DEBRIS IN THE GUTTER (7505A.4)
 4. (ROOF) (ATTIC) EXTERIOR WALL VENTS SHALL RESET THE OUTRUSH OF FLAME AND ENTERS INTO THE ATTIC AREA OF THE STRUCTURE. OR SHALL BE PROTECTED BY CORROSION-RESISTANT NONCOMBUSTIBLE WIRE MESH WITH 1/4 INCH (6.35 MM) OPENINGS OR ITS EQUIVALENT. VENTS SHALL NOT BE INSTALLED IN EAVES AND CORNICES (7506A.1, 7506A.2, 7506A.3, 7506I.3)
 5. EAVES AND ROOF EDS SHALL MEET THE REQUIREMENTS OF SPH 12-7A-2 OR SHALL BE PROTECTED BY CORROSION-RESISTANT MATERIALS OR NONCOMBUSTIBLE CONSTRUCTION ON THE EXPOSED UNDERSIDE (7507A.5)
 6. EXTERIOR WALLS SHALL BE APPROVED NONCOMBUSTIBLE OR CORROSION-RESISTANT MATERIAL, HEAVY TIMBER, OR LUG WALL CONSTRUCTION OR SHALL PROVIDE PROTECTION FROM THE INTRUSION OF FLAMES AND ENTERS IN ACCORDANCE WITH STANDARD SPH 12-1A-1 (7508A.3)
 7. EXTERIOR WALL COVERINGS SHALL EXTEND FROM THE TOP OF FOUNDATION TO THE ROOF, AND TERMINATE AT 2-INCH DIA. FINI NORMAL SLOD WOOD BLOCKING BETWEEN RAFTERS AT ALL ROOF OVERLAPS, OR IN THE CASE OF ENCLOSED EAVES, TERMINATE AT THE ENCLOSURE (7508A.3.2)
 8. EXTERIOR WINDOWS, WINDOW WALLS, GLAZE DOORS, AND GLAZED OPENINGS WITHIN EXTERIOR DOORS SHALL BE INSULATING, GLASS UNITS WITH A MINIMUM OF ONE TEMPERED PANE OR GLASS BLOCK UNITS, OR HAVE A FIRE-RESISTANCE RATING OF NOT LESS THAN 20 MINUTES, WHEN TESTED ACCORDING TO WPA 101, OR CONFORM TO THE PERFORMANCE REQUIREMENTS OF SPH 12-7A-2 (7508A.2.0)
 9. EXTERIOR DOOR ASSEMBLIES SHALL CONFORM TO THE PERFORMANCE REQUIREMENTS OF STANDARD SPH 12-7A-1 OR SHALL BE APPROVED NONCOMBUSTIBLE CONSTRUCTION, OR SOLID CORE WOOD HAVING STILES AND SHALL NOT LESS THAN 1 3/4 INCHES THICK WITH INTERIOR FILL PANEL THICKNESS NO LESS THAN 1 1/4 INCHES THICK, OR SHALL HAVE A FIRE-RESISTANCE RATING OF NOT LESS THAN 20 MINUTES WHEN TESTED ACCORDING TO ASTM A 215 (EXCEPTION NONCOMBUSTIBLE OR EXTERIOR FIRE-RETARDANT TREATED WOOD VEHICLE ACCESS DOORS) (7508A.3)
 10. DECKING, SURFACES, STAIR TREADS, RISERS, AND LANDINGS OF DECKS, PORCHES, AND BALCONIES WHERE ANY PORTION OF SUCH SURFACE IS WITHIN 10 FEET (3.05 M) OF THE PRIMARY STRUCTURE SHALL BE CONSTRUCTED OF HEAVY TIMBER, NON COMBUSTIBLE OR OTHER APPROVED MATERIALS PER 512.708A.3
 11. THE UNDERSIDE OF CANTILEVERED AND OVERHANGING APPENDAGES AND FLOOR PROJECTIONS SHALL HANGFIRE, THE DOWNFIRE-RESISTANT WEIRITY OF EXTERIOR WALLS, OR THE PROJECTION SHALL BE ENCLOSED TO THE GRADE (7510A.1)
 12. BUILDINGS SHALL HAVE ALL UNDERFLOOR AREAS COMPLETELY ENCLOSED TO THE GRADE WITH CONSTRUCTION AS REQUIRED FOR EXTERIOR WALLS (7510A.8, 7507I)
 13. ALL UTILITIES, PIPES, FURNACES, WATER HEATERS OR OTHER MECHANICAL DEVICES LOCATED IN AN EXPOSED UNDER-FLOOR AREA OF A RESIDENTIAL BUILDING SHALL BE ENCLOSED WITH MATERIALS AS REQUIRED FOR 1-HOUR FIRE-RESISTIVE CONSTRUCTION. (7207.2)
 14. THE SPACE BETWEEN THE ROOF COVERING AND ROOF DECKING SHALL BE CONSTRUCTED TO PREVENT THE INTRUSION OF FLAMES AND ENTERS AND BE FIRE STOPPED FOR 7504.5

PROJECT:
CLIFF RESIDENCE PROJECT
 1236 N CLIFF DR
 LOS ANGELES, CA 90065

OWNER:
 AS THE CROW, LLC
 2831 4TH STREET
 SANTA MONICA, CA 90405
 TEL: +1 (310) 448-8508
 HALLIE@CROW.COM

DESIGNER:
 HALLIE BLACK
 2737 HILLGROVE DRIVE
 TORANCA, CA 90503
 TEL: +1 (310) 791-1300
 HALLIE@HBLACK.COM

EXECUTIVE ARCHITECT:
 ARCHITECTURE
 STUDIO SEO PLLC
 308 W 5TH ST, 12
 NEW YORK, NY 10012
 TEL: +1 (212) 761-1300
 CONTACT@STUDIOSEO.COM

CIVIL ENGINEER:
 WEST COAST TECHNICAL
 CONSULTANTS, INC.
 1001 EAST LOS ANGELES AVE, C15
 SAN VALLEY, CA 90055
 TEL: +1 (800) 274-9544
 CATH@WCTC.COM

STRUCTURE ENGINEER:
 POLON & LEWIS
 STRUCT ENGINEERING, INC.
 5301 BEECHER ST, STE 300
 LOS ANGELES, CA 90044
 TEL: +1 (310) 798-5411
 OFFICE@POLON-LEWIS.COM



ISSUES / REVISIONS

DATE	SYMBOL	DESCRIPTION
2024-05-09		SUBMISSION
2024-03-21		REVISION 1
2024-02-10		REVISION 2
2024-01-09		FILED
2024-01-09		FILED REVISION 1

LABOR APPROVAL STAND

EXHIBIT "A"
 Page No. 9 of 17
 Case No. 24-001-2016-CUL-SHPC-HCA

FLOOR PLAN - ROOF
 SCALE: FULL (1/4"=1'-0")
 01.10.2025

CITY OF LOS ANGELES, DEPARTMENT OF BUILDING AND SAFETY
 PRELIMINARY ZONING ASSESSMENT COMPLETE
 BY: RONALD GREENE
 DATE: 07/10/2025
 APPLICATION #: 24001-10001-000008

PROJECT NUMBER: 0003KLI
 PHASE: 2000/PERMITTING REVIEW
 DATE: 07/07/2025
 SCALE: 1/4" = 1'-0"

FLOOR PLAN
ROOF
A-103.0

**CLIFF
RESIDENCE
PROJECT
NEW CONSTRUCTION**

PROJECT ADDRESS:
APN5454013026
1236 N CLIFF DR
LOS ANGELES, CA 90065

OWNER:
AS THE CROW, LLC
7234 4TH STREET
SANTA MONICA, CA 90405
TEL: +1 (310) 449-8908
HALLIE.BLACK@GMAIL.COM

DESIGNER:
HALLIE BLACK
7237 HILLSIDE DRIVE
TOPANGA, CA 90230
TEL: +1 (310) 449-8908
HALLIE.BLACK@GMAIL.COM

EXECUTIVE ARCHITECT:
**ARCHITECTURE
STUDIO SEO PLLC**
308 W 82ND ST, 3RD
NEW YORK, NY 10024
TEL: +1 (212) 795-1300
CONGUSTUDIOSEO.COM

ENV. ENGINEER:
**WEST COAST TECHNICAL
CONSULTANTS, INC.**
197 EAST LOS ANGELES AVE, 6TH
SUN VALLEY, CA 91355
TEL: +1 (818) 251-0564
DAVID@WTCINC.COM

STRUCTURE ENGINEER:
**POLON & LEWIS
STRUCT. ENGINEERING, INC.**
5300 BECHTOLD ST., STE 300
LOS ANGELES, CA 90066
OFFICE@POLON-LEWIS.COM



ISSUES / REVISIONS

DATE	SYMBOL	DESCRIPTION
07/10/2025		REVISION 1
07/10/2025		REVISION 2
07/10/2025		REVISION 3
07/10/2025		REVISION 4
07/10/2025		REVISION 5
07/10/2025		REVISION 6
07/10/2025		REVISION 7
07/10/2025		REVISION 8
07/10/2025		REVISION 9
07/10/2025		REVISION 10


LABOR APPROVAL STAMP

CITY OF LOS ANGELES, DEPARTMENT OF BUILDING AND SAFETY

PRELIMINARY ZONING ASSESSMENT COMPLETE
BY: RONALD GREENE
DATE: 07/10/2025
APPLICATION #: 240115-130001 - 000002

PROJECT NUMBER: 00000001
PHASE: ZONING/PERMITTING REVIEW
DATE: 07/10/2025
SCALE: 1/4" = 1'-0"

EAST ELEVATION
WEST ELEVATION
A-200.0



PROJECT
CLIFF
RESIDENCE
PROJECT
NEW CONSTRUCTION

PROJECT ADDRESS:
APN5454013026
1236 N CLIFF DR
LOS ANGELES, CA 90065


OWNER:
AS THE CROW, LLC
2414 4TH STREET
SANTA MONICA, CA 90401
TEL: +1 310 443-8519
HALLIE@BLACKBOX.COM

DESIGNER:
HALLIE BLACK
2127 HILLSIDE DRIVE
TOPANGA, CA 90901
TEL: +1 310 443-8519
HALLIE@BLACKBOX.COM

EXECUTIVE ARCHITECT:
ARCHITECTURE
STUDIO SEO PLLC
308 W 8TH ST, 100
NEW YORK, NY 10013
TEL: +1 212 255-1100
DOBOS@STUDIOSEO.COM

CIVIL ENGINEER:
WEST COAST TECHNICAL
CONSULTANTS, INC
1001 EAST LOS ANGELES AVE, 110
SUN VALLEY, CA 91350
TEL: +1 818 260-0000
DAVID@WCTC.COM

STRUCTURE ENGINEER:
POLON & LEWIS
STRUCT ENGINEERING, INC
5301 REITHOVEN ST, STE 200
LOS ANGELES, CA 90064
TEL: +1 310 780-0401
OFFICE@POLON-LEWIS.COM



ISSUES / REVISIONS			
DATE	SYMBOL	DESCRIPTION	
2024-05-09		SUBMISSION	
2025-03-28		REVISION 1	
2025-04-30		REVISION 2	
2025-05-09		FILING	
2025-05-30		FILING	REVISION 1

CLIFF RESIDENCE NORTH



B1 - WEST ELEVATION WITH FRONT ENTRY LOOKING EAST FROM CLIFF DR



B2 - NORTH AND EAST ELEVATION LOOKING SOUTH WEST FROM CLIFF DR



B3 - WEST AND EAST ELEVATIONS LOOKING NORTH FROM CLIFF RESIDENCE SOUTH

EXHIBIT "A"
Page No. 12 of 17
Case No. 2A-2025-2866-CLIFF-SPAC-HCA

CLIFF RESIDENCE PROJECT NEW CONSTRUCTION

PROJECT ADDRESS
APN5454013026
1236 N CLIFF DR
LOS ANGELES, CA 90065

OWNER
AS THE CROW, LLC
2424 4TH STREET
SANTA MONICA, CA 90405
TEL: +1 310 345-4545
HALLIE.BLACK@HMC.COM

DESIGNER
HALLIE BLACK
2022 HILLSDALE DRIVE
TOPANMA, CA 92390
TEL: +1 951 345-4545
HALLIE.BLACK@HMC.COM

EXECUTIVE ARCHITECT
ARCHITECTURE
STUDIO SEO PLLC
346 W 17TH ST, 10
NEW YORK, NY 10011
TEL: +1 212 345-4545
GORDON@STUDIOSEO.COM

CIVIL ENGINEER
WEST COAST TECHNICAL
CONSULTANTS, INC
193 EAST LOS ANGELES AVE, C15
SUN VALLEY, CA 91355
TEL: +1 818 246-4544
DAVID@WCTCONE.COM

STRUCTURE ENGINEER
POLON & LEWIS
STRUCT ENGINEERING, INC
5301 BEETHOVEN ST, STE 200
LOS ANGELES, CA 90044
TEL: +1 310 546-5811
OFFICE@POLON-LEWIS.COM



DATE	SYMBOL	DESCRIPTION
2024-05-09		SUBMISSION
2025-03-27		REVISION 1
2025-01-08		REVISION 2
2025-05-01		FINAL
2025-05-01		FINAL REVISION 1

LABOR APPROVAL STAMP

PROJECT NUMBER: 000001
PHASE: ZONING/PERMITTING REVIEW
DATE: 03/03/2025
SCALE: NA

RENDERING
B-001.0



IVMHSZ NOTES

- [illegible]

PROJECT:
CLIFF
RESIDENCE
PROJECT
1236 N CLIFF DR
LOS ANGELES, CA 90065

OWNER:
AS THE CROW, LLC
2634 8TH STREET
SANTA MONICA, CA 90405
TEL: +1 (617) 449-8510
HALLIE.BLACK@ATC.COM

DESIGNER:
HALLIE BLACK
21377 HILLSIDE DRIVE
TOPANGA, CA 90270
TEL: +1 (417) 649-8518
HALLIE.BLACK@HCL.COM

EXECUTIVE ARCHITECT:
ARCHITECTURE
STUDIO SEO PLLC
305 W 82ND ST, 11D
NEW YORK, NY 10024
TEL: +1 (212) 795-3300
6060STUDIOSEO.COM

CIVIL ENGINEER:
WEST COAST TECHNICAL
CONSULTANTS, INC
1097 EAST LOS ANGELES AVE, CTS
SUN VALLEY, CA 93005
TEL: +1 (818) 216-0904
DAVID@WCTCINC.COM

STRUCTURE ENGINEER:
POLON & LEWIS
STRUCT ENGINEERING, INC.
5301 BIETHOVEN ST., STE 200
LOS ANGELES, CA 90066
TEL: (310) 998-5611
OFFICE@POLONLEWIS.COM

REV. 01-03-00



ISSUES / REVISIONS		
DATE	SYMBOL	DESCRIPTION
2024-05-09		SUBMISSION
2025-03-21		REVISION 1
2025-06-10		REVISION 0
2025-05-09		FR.040
2025-05-30		FR.040 REVISION 1

PROJECT NUMBER: 00031CL
PHASE: ZONING/PERMITTING REVIEW
DATE: 07/02/2025
SCALE: 1/4" = 1'-0"

FLOOR PLAN
BASEMENT
B-101.0

EXHIBIT "A"
Page No. 13 of 17
Case No. ZA-2025-2856-CU1-SPPC-HCA

A1 FLOOR PLAN - BASEMENT

**CLIFF
RESIDENCE
PROJECT**

APN 545-013026
7236 N CLIFF DR
LOS ANGELES, CA 90045

OWNER:
AS THE GROW LLC
SANTA MONICA, CA 90405
HALLIE BLACK ARCHITECT
HALLIEBLACKARCHITECT.COM

DESIGNER:
HALLIE BLACK
HALLIEBLACKARCHITECT.COM

EXECUTIVE ARCHITECT:
ARCHITECTURE
STUDIO SEO PLLC
NEW YORK, NY 10012
100-2113000000

WEST COAST TECHNICAL
CONSULTANTS, INC.
100 EAST 6TH AVENUE
LOS ANGELES, CA 90012
TEL: 310-261-2600
WWW.WCTC-INC.COM

STRUCTURE ENGINEER:
PULON & LEWIS
STRUCTURAL ENGINEERING, INC.
5811 WESTERN ST., STE. 200
LOS ANGELES, CA 90045
TEL: 310-394-9444
WWW.PULON-LEWIS.COM

KEY PLAN



DATE	REVISION	DESCRIPTION
08/15/14	1	SUBMISSION
09/15/14	2	REVISION 1
10/15/14	3	REVISION 2
11/15/14	4	REVISION 3
12/15/14	5	REVISION 4
01/15/15	6	REVISION 5
02/15/15	7	REVISION 6
03/15/15	8	REVISION 7
04/15/15	9	REVISION 8
05/15/15	10	REVISION 9
06/15/15	11	REVISION 10
07/15/15	12	REVISION 11
08/15/15	13	REVISION 12
09/15/15	14	REVISION 13
10/15/15	15	REVISION 14
11/15/15	16	REVISION 15
12/15/15	17	REVISION 16
01/15/16	18	REVISION 17
02/15/16	19	REVISION 18
03/15/16	20	REVISION 19
04/15/16	21	REVISION 20
05/15/16	22	REVISION 21
06/15/16	23	REVISION 22
07/15/16	24	REVISION 23
08/15/16	25	REVISION 24
09/15/16	26	REVISION 25
10/15/16	27	REVISION 26
11/15/16	28	REVISION 27
12/15/16	29	REVISION 28
01/15/17	30	REVISION 29
02/15/17	31	REVISION 30
03/15/17	32	REVISION 31
04/15/17	33	REVISION 32
05/15/17	34	REVISION 33
06/15/17	35	REVISION 34
07/15/17	36	REVISION 35
08/15/17	37	REVISION 36
09/15/17	38	REVISION 37
10/15/17	39	REVISION 38
11/15/17	40	REVISION 39
12/15/17	41	REVISION 40
01/15/18	42	REVISION 41
02/15/18	43	REVISION 42
03/15/18	44	REVISION 43
04/15/18	45	REVISION 44
05/15/18	46	REVISION 45
06/15/18	47	REVISION 46
07/15/18	48	REVISION 47
08/15/18	49	REVISION 48
09/15/18	50	REVISION 49
10/15/18	51	REVISION 50
11/15/18	52	REVISION 51
12/15/18	53	REVISION 52
01/15/19	54	REVISION 53
02/15/19	55	REVISION 54
03/15/19	56	REVISION 55
04/15/19	57	REVISION 56
05/15/19	58	REVISION 57
06/15/19	59	REVISION 58
07/15/19	60	REVISION 59
08/15/19	61	REVISION 60
09/15/19	62	REVISION 61
10/15/19	63	REVISION 62
11/15/19	64	REVISION 63
12/15/19	65	REVISION 64
01/15/20	66	REVISION 65
02/15/20	67	REVISION 66
03/15/20	68	REVISION 67
04/15/20	69	REVISION 68
05/15/20	70	REVISION 69
06/15/20	71	REVISION 70
07/15/20	72	REVISION 71
08/15/20	73	REVISION 72
09/15/20	74	REVISION 73
10/15/20	75	REVISION 74
11/15/20	76	REVISION 75
12/15/20	77	REVISION 76
01/15/21	78	REVISION 77
02/15/21	79	REVISION 78
03/15/21	80	REVISION 79
04/15/21	81	REVISION 80
05/15/21	82	REVISION 81
06/15/21	83	REVISION 82
07/15/21	84	REVISION 83
08/15/21	85	REVISION 84
09/15/21	86	REVISION 85
10/15/21	87	REVISION 86
11/15/21	88	REVISION 87
12/15/21	89	REVISION 88
01/15/22	90	REVISION 89
02/15/22	91	REVISION 90
03/15/22	92	REVISION 91
04/15/22	93	REVISION 92
05/15/22	94	REVISION 93
06/15/22	95	REVISION 94
07/15/22	96	REVISION 95
08/15/22	97	REVISION 96
09/15/22	98	REVISION 97
10/15/22	99	REVISION 98
11/15/22	100	REVISION 99
12/15/22	101	REVISION 100
01/15/23	102	REVISION 101
02/15/23	103	REVISION 102
03/15/23	104	REVISION 103
04/15/23	105	REVISION 104
05/15/23	106	REVISION 105
06/15/23	107	REVISION 106
07/15/23	108	REVISION 107
08/15/23	109	REVISION 108
09/15/23	110	REVISION 109
10/15/23	111	REVISION 110
11/15/23	112	REVISION 111
12/15/23	113	REVISION 112
01/15/24	114	REVISION 113
02/15/24	115	REVISION 114
03/15/24	116	REVISION 115
04/15/24	117	REVISION 116
05/15/24	118	REVISION 117
06/15/24	119	REVISION 118
07/15/24	120	REVISION 119
08/15/24	121	REVISION 120
09/15/24	122	REVISION 121
10/15/24	123	REVISION 122
11/15/24	124	REVISION 123
12/15/24	125	REVISION 124
01/15/25	126	REVISION 125
02/15/25	127	REVISION 126
03/15/25	128	REVISION 127
04/15/25	129	REVISION 128
05/15/25	130	REVISION 129
06/15/25	131	REVISION 130
07/15/25	132	REVISION 131
08/15/25	133	REVISION 132
09/15/25	134	REVISION 133
10/15/25	135	REVISION 134
11/15/25	136	REVISION 135
12/15/25	137	REVISION 136
01/15/26	138	REVISION 137
02/15/26	139	REVISION 138
03/15/26	140	REVISION 139
04/15/26	141	REVISION 140
05/15/26	142	REVISION 141
06/15/26	143	REVISION 142
07/15/26	144	REVISION 143
08/15/26	145	REVISION 144
09/15/26	146	REVISION 145
10/15/26	147	REVISION 146
11/15/26	148	REVISION 147
12/15/26	149	REVISION 148
01/15/27	150	REVISION 149
02/15/27	151	REVISION 150
03/15/27	152	REVISION 151
04/15/27	153	REVISION 152
05/15/27	154	REVISION 153
06/15/27	155	REVISION 154
07/15/27	156	REVISION 155
08/15/27	157	REVISION 156
09/15/27	158	REVISION 157
10/15/27	159	REVISION 158
11/15/27	160	REVISION 159
12/15/27	161	REVISION 160
01/15/28	162	REVISION 161
02/15/28	163	REVISION 162
03/15/28	164	REVISION 163
04/15/28	165	REVISION 164
05/15/28	166	REVISION 165
06/15/28	167	REVISION 166
07/15/28	168	REVISION 167
08/15/28	169	REVISION 168
09/15/28	170	REVISION 169
10/15/28	171	REVISION 170
11/15/28	172	REVISION 171
12/15/28	173	REVISION 172
01/15/29	174	REVISION 173
02/15/29	175	REVISION 174
03/15/29	176	REVISION 175
04/15/29	177	REVISION 176
05/15/29	178	REVISION 177
06/15/29	179	REVISION 178
07/15/29	180	REVISION 179
08/15/29	181	REVISION 180
09/15/29	182	REVISION 181
10/15/29	183	REVISION 182
11/15/29	184	REVISION 183
12/15/29	185	REVISION 184
01/15/30	186	REVISION 185
02/15/30	187	REVISION 186
03/15/30	188	REVISION 187
04/15/30	189	REVISION 188
05/15/30	190	REVISION 189
06/15/30	191	REVISION 190
07/15/30	192	REVISION 191
08/15/30	193	REVISION 192
09/15/30	194	REVISION 193
10/15/30	195	REVISION 194
11/15/30	196	REVISION 195
12/15/30	197	REVISION 196
01/15/31	198	REVISION 197
02/15/31	199	REVISION 198
03/15/31	200	REVISION 199
04/15/31	201	REVISION 200
05/15/31	202	REVISION 201
06/15/31	203	REVISION 202
07/15/31	204	REVISION 203
08/15/31	205	REVISION 204
09/15/31	206	REVISION 205
10/15/31	207	REVISION 206
11/15/31	208	REVISION 207
12/15/31	209	REVISION 208
01/15/32	210	REVISION 209
02/15/32	211	REVISION 210
03/15/32	212	REVISION 211
04/15/32	213	REVISION 212
05/15/32	214	REVISION 213
06/15/32	215	REVISION 214
07/15/32	216	REVISION 215
08/15/32	217	REVISION 216
09/15/32	218	REVISION 217
10/15/32	219	REVISION 218
11/15/32	220	REVISION 219
12/15/32	221	REVISION 220
01/15/33	222	REVISION 221
02/15/33	223	REVISION 222
03/15/33	224	REVISION 223
04/15/33	225	REVISION 224
05/15/33	226	REVISION 225
06/15/33	227	REVISION 226
07/15/33	228	REVISION 227
08/15/33	229	REVISION 228
09/15/33	230	REVISION 229
10/15/33	231	REVISION 230
11/15/33	232	REVISION 231
12/15/33	233	REVISION 232
01/15/34	234	REVISION 233
02/15/34	235	REVISION 234
03/15/34	236	REVISION 235
04/15/34	237	REVISION 236
05/15/34	238	REVISION 237
06/15/34	239	REVISION 238
07/15/34	240	REVISION 239
08/15/34	241	REVISION 240
09/15/34	242	REVISION 241
10/15/34	243	REVISION 242
11/15/34	244	REVISION 243
12/15/34	245	REVISION 244
01/15/35	246	REVISION 245
02/15/35	247	REVISION 246
03/15/35	248	REVISION 247
04/15/35	249	REVISION 248
05/15/35	250	REVISION 249
06/15/35	251	REVISION 250
07/15/35	252	REVISION 251
08/15/35	253	REVISION 252
09/15/35	254	REVISION 253
10/15/35	255	REVISION 254
11/15/35	256	REVISION 255
12/15/35	257	REVISION 256
01/15/36	258	REVISION 257
02/15/36	259	REVISION 258
03/15/36	260	REVISION 259
04/15/36	261	REVISION 260
05/15/36	262	REVISION 261
06/15/36	263	REVISION 262
07/15/36	264	REVISION 263
08/15/36	265	REVISION 264
09/15/36	266	REVISION 265
10/15/36	267	REVISION 266
11/15/36	268	REVISION 267
12/15/36	269	REVISION 268
01/15/37	270	REVISION 269
02/15/37	271	REVISION 270
03/15/37	272	REVISION 271
04/15/37	273	REVISION 272
05/15/37	274	REVISION 273
06/15/37	275	REVISION 274
07/15/37	276	REVISION 275
08/15/37	277	REVISION 276
09/15/37	278	REVISION 277
10/15/37	279	REVISION 278
11/15/37	280	REVISION 279
12/15/37	281	REVISION 280
01/15/38	282	REVISION 281
02/15/38	283	REVISION 282
03/15/38	284	REVISION 283
04/15/38	285	REVISION 284
05/15/38	286	REVISION 285
06/15/38	287	REVISION 286
07/15/38	288	REVISION 287
08/15/38	289	REVISION 288
09/15/38	290	REVISION 289
10/15/38	291	REVISION 290
11/15/38	292	REVISION 291
12/15/38	293	REVISION 292
01/15/39	294	REVISION 293
02/15/39	295	REVISION 294
03/15/39	296	REVISION 295
04/15/39	297	REVISION 296
05/15/39	298	REVISION 297
06/15/39	299	REVISION 298
07/15/39	300	REVISION 299
08/15/39	301	REVISION 300
09/15/39	302	REVISION 301
10/15/39	303	REVISION 302
11/15/39	304	REVISION 303
12/15/39	305	REVISION 304
01/15/40	306	REVISION 305
02/15/40	307	REVISION 306
03/15/40	308	REVISION 307
04/15/40	309	REVISION 308
05/15/40	310	REVISION 309
06/15/40	311	REVISION 310
07/15/40	312	REVISION 311
08/15/40	313	REVISION 312
09/15/40	314	REVISION 313
10/15/40	315	REVISION 314
11/15/40	316	REVISION 315
12/15/40	317	REVISION 316
01/15/41	318	REVISION 317
02/15/41	319	REVISION 318
03/15/41	320	REVISION 319
04/15/41	321	REVISION 320
05/15/41	322	REVISION 321
06/15/41	323	REVISION 322
07/15/41	324	REVISION 323
08/15/41	325	REVISION 324
09/15/41	326	REVISION 325
10/15/41	327	REVISION 326
11/15/41	328	REVISION 327
12/15/41	329	REVISION 328
01/15/42	330	REVISION 329
02/15/42	331	REVISION 330
03/15/42	332	REVISION 331
04/15/42	333	REVISION 332
05/15/42	334	REVISION 333
06/15/42	335	REVISION 334
07/15/42	336	REVISION 335
08/15/42	337	REVISION 336
09/15/42	338	REVISION 337
10/15/42	339	REVISION 338
11/15/42	340	REVISION 339
12/15/42	341	REVISION 340
01/15/43	342	REVISION 341
02/15/43	343	REVISION 342
03/15/43	344	REVISION 343
04/15/43	345	REVISION 344
05/15/43	346	REVISION 345
06/15/43	347	REVISION 346
07/15/43	348	REVISION 347
08/15/43	349	REVISION 348
09/15/43		

PROJECT ADDRESS:
APN5454013026
1236 N CLIFF DR
LOS ANGELES, CA 90065

OWNER:
AS THE CROW, LLC
2636 6TH STREET
SANTA MONICA, CA 90405
TEL: +1 (617) 459-8518
MALLIE@BLACKBIRD.COM

DESIGNER:
HALLIE BLACK
21321 HILLSIDE DRIVE
TOPANGA, CA 90290
TEL: +1 (617) 449-8518
HALLIEBLACK@GMAIL.COM

EXECUTIVE ARCHITECT:
ARCHITECTURE
STUDIO SEO PLLC
300 W 82ND ST, 8D
NEW YORK, NY 10024
TEL: +1 (212) 795-3300
GO@GOSTUDIOSEO.COM

CIVIL ENGINEER
WEST COAST TECHNICAL
CONSULTANTS, INC
1197 EAST 105 ANGELES AVE, C115
SUN VALLEY, CA 91365
TEL: +1 (818) 216-8504
DAVID@WCTCINC.COM

STRUCTURE ENGINEER
POLON & LEWIS
STRUCT ENGINEERING, INC
5301 BEETHOVEN ST. STE 200
LOS ANGELES, CA 90046
TEL. +1 (310) 970-5671
OFFICE@POLON-LEWIS.COM

KEY PLAN:



ISSUES / REVISIONS		
DATE	SYMBOL	DESCRIPTION
2024-05-09		SUBMISSION
2025-03-21		REVISION 7
2025-04-10		REVISION 8
2025-05-09		PENDING
2025-05-10		PENDING REVISION 1


LADD'S APPROVAL STAMP




CITY OF LOS ANGELES, DEPARTMENT
OF BUILDING AND SAFETY
PRELIMINARY ZONING ASSESSMENT COMPLETE
BY: RONALD GREENE
DATE: 07/10/2005
APPLICATION #: 24016 - 10001 - 02022


PROJECT NUMBER: 0003KLI
PHASE: ZONING/PERMITTING R
DATE: 07/02/2025
SCALE: 1/4" = 1'-0"

EAST ELEVATION
SOUTH ELEVATION
B-200.0





A3 NORTH ELEVATION
SCALE - FULL (1/8"=1'-0") 1/4" x 7'-0" CU-B-ELE



A1 WEST ELEVATION
SCALE - FULL (1/8"=1'-0") 1/4" x 7'-0" CU-B-ELE

EXHIBIT "A"
Page No. 17 of 17
Case No. 2A-2025-2856-CUI-SPCH-1

PROJECT
CLIFF
RESIDENCE
PROJECT
NEW CONSTRUCTION

PROJECT ADDRESS:
APN5454013026
1236 N CLIFF DR
LOS ANGELES, CA 90065

OWNER:
AS THE CROW, LLC
2634 6TH STREET
SANTA MONICA, CA 90405
TEL: +1 (310) 419-8518
HALLIEBLACK.COM

DESIGNER:
HALLIE BLACK
27133 HALLIE DRIVE
TOPANGA, CA 91329
TEL: +1 (818) 445-8518
HALLIEBLACK.COM

EXECUTIVE ARCHITECT:
ARCHITECTURE
STUDIO SEO PLLC
300 W 2ND ST, 10
NEW YORK, NY 10013
TEL: +1 (212) 795-1398
GOOGLE.COM

CIVIL ENGINEER:
WEST COAST TECHNICAL
CONSULTANTS, INC
1917 EAST LOS ANGELES AVE, CTS
SUN VALLEY, CA 91355
TEL: +1 (818) 378-0504
DAVID@WCTECH.COM

STRUCTURE ENGINEER:
POLON & LEWIS
STRUCT ENGINEERING, INC
5381 BEECHVIEW ST, STE 208
LOS ANGELES, CA 90048
TEL: +1 (310) 798-5811
OFFICE@POLON-LEWIS.COM



ISSUES / REVISIONS:

DATE	SYMBOL	DESCRIPTION
2024-05-03		SUBMISSION
2025-05-11		REVISION 1
2025-05-11		REVISION 2
2025-05-11		REVISION 3
2025-05-11		REVISION 4
2025-05-11		REVISION 5

LAURE APPROVAL STAMP:



PROJECT NUMBER: 0001CU
PHASE: ZONING/PERMITTING REVIEW
DATE: 07/10/2025
SCALE: 1/4" x 7'-0"

WEST ELEVATION
NORTH ELEVATION
B-201.0